

SCOPE:Excavate to remove existing G4 material,supply new G4 material compacted to 97% standard ModAashto density to ground level,supply and apply primer followed by hot-mix asphalt

Item	Description	Unit	Qty	Rate	Amount
1	P's and G's	sum	1		
2	SHEQ	sum	1		
3	Provide cable detector to check positions and levels of all buried/underground cables,also chec for all buried pipes around area of work	sum	1		
6	Close road by visible barraicate and signage ,machine excavate to a depth of 10m around manhole,sloped at entry point into hole	mqb	196		
12	Import G4 material from commercial sources and backfill in 150mm layers compacted to 97% standard ModAahto debsity till ground level	mqb	191,,32		
13	Apply primer followed by hot-mix asphalt rolled eith BOMAG	sum	1		
14	Re-instate overhead shelter	ea	1		
15	Supply and lay 800mm thick interlocking paveblocks	msq	30		
16	Regrassing including fertilizers	msq	20		
				TOTAL	