

SCOPE:Re-instatement Of Collapsed Structure Above Sicon Discharge Chute (FAB1)

Item	Description	Unit	Qty	Rate
1	Preliminary And Generals	sum	1	
2	Health and safety	sum	1	
3	,Remove bent IBR sheets and dismantled structure and dispose to a suitable dumping site	sum	1	
4a	Supply 125 x 75 x 2mm Lipped Channels purlins	m	60	
4b	Supply 200 x 75 mm Z-channels	m	66	
4c	Supply 500 x 150mm I-SECTION bend as per plan	m	21	
5	Supply 80 X 80 X 8mm angle iron for bracing	m	37.2	
6a	Supply 6 X 0.7 X 8mm Thick IBR Sheets and 10m X 8mm galvanised flashing including Hex Head Tek Screws at 7 n0 fo screws per metre	ea.	30	
6b	Supply 6000 x 700mm Transluscent sheets	ea.	2	
7	Installation of the above	sum	1	
8	Provide 80 Ton mobile crane	sum	1	
9	Provide RP to take out permit to work	sum	1	
				Total

