

Date:
21 July 2022

Enquiries:
Shilo Motuku
Tel +27 13 647 9188
Fax +27 86 537 3516
Email shilo.motuku@eskom.co.za

PART 2

CLARIFICATIONS - ENQUIRY NO. MPKEN10276GX

DESCRIPTION: - FOR THE REMOVAL AND REPLACEMENT OF SUPERHEATER FRONT PENDANT FINISHING RUL TUBES AT KENDAL POWER STATION UNIT 1 AND 3 GO.

Supplier Clarification	Eskom Response
1.1 Will Eskom free issue already manipulated tubes for rows 15 to 25 on element? 1.2 Manipulations of tube are done by others and not a deliverable from the contractor?	1.1 This scope will not be done. 1.3 This scope will not be executed
2.1 Will Eskom free issue swage pieces that are swaged, cut to length with ends prepped? 2.2 My mistake, instead of swage pieces it should be transition pieces. Please confirm that the transition pieces will be issued to contractor already cut to the length of 150mm?	2.1 All spares will be free issued by Eskom 2.2 No They will be issued in 6metre length the contractor will cut to size and weld
2 On the prefabrication is the contractor responsible for the AIA cost or will Eskom provide the AIA?	Eskom will provide AIA