

Priced Bills of Quantities for Majuba Road Rehabilitation

8		SECTION 1 : NLEPDS FENCING				
		Lethabo P/S Solar PV Plant Fence	UoM	Quantity	Rate	Amount
8,2	SABS 1200 C	SITE CLEARANCE				
8.2.1		Clear & grub fence (1000mm width)	m²	23 358,00		
8,3	SABS 1200 DM	CIVIL WORKS				
		EXCAVATION				
8.3.1		Excavate 500x500x650mm deep Straining post pit	m3	381,00		
8.3.2		Excavate 200x600mm deep anti-burrowing	m3	2 534,00		
		CONCRETE				
8.3.3		20MPa Mass concrete				
		Posts	m3	381,00		
		Anti-burrowing	m3	2 534,00		
8,4	SABS 1220 DM	FENCING				
		HIGH RISK SECURITY MESH FENCING				
8.4.1		The fence will be dressed with an Y electric wire on top				
8.4.2		2,4m Post @10m c/c	no	1 558,00		
8.4.3		2,4m Poly*** mesh fence	m	15 572,00		
8.4.4		Non-Lethal Electric fence	m	7 786,00		
		GATES				
8.4.5		Pedestrian gate	no.	2,00		
8.4.6		8m wide motorized mesh fence gate for vehicle	no.	2,00		
		TOTAL SECTION 1				-