

PLAN
SCALE 1:250

CO-ORDINATE LIST – WGS 84 FENCE SETTING-OUT POINTS		
POINT	X (m)	Y (m)
P1	3 129 791.739	-57 643.812
P2	3 129 746.067	-57 637.869
P3	3 129 737.616	-57 619.657
P4	3 129 747.679	-57 600.500
P5	3 129 765.539	-57 600.809
P6	3 129 797.534	-57 632.737
P7	3 129 796.484	-57 634.734
P8	3 129 793.297	-57 640.842
P9	3 129 792.249	-57 642.838

Summary:


- 1 x Type A
- 1 x Boom
- 2 x Security CCTV

Type A:
Biometric in, Card out, Door status, Break glass, CCTV
Interfaced to door motors

1. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT FENCE DRAWINGS: 10 103 to 10 111
2. FENCE POSITIONS TO BE FINALIZED ON SITE BY THE SUPERVISOR UPON COMPLETION OF REHABILITATION

ISSUED FOR
CONSTRUCTION
DATE : 10/12/2013

BCJV AUTH BY : K. GEORGALA
BCJV APP BY : C. LOGANI
ESKOM APP BY : D. PADAYACHEE



UNDERGROUND WORKS

FOR REFERENCE DRAWINGS, REFER TO DRAWING 24 10a

KKS	AUTH BY	
BRAAMHOEK CONSULTANTS JOINT VENTURE		
ARCUS GIEB		
SSI		
Knight Priced		
INGULA PUMPED STORAGE SCHEME		
MAIN ACCESS TUNNEL		
PORTAL EXTENSION		
FENCE LAYOUT		
0.83/24 561		
SHEET 1		
0		