

**ESKOM ROTEK INDUSTRIES CONSTRUCTION SERVICES
TRANSMISSION**

SUPPLY OF BUSHCLEARING SERVICES


| ITEM | DESCRIPTION | Unit | Qty | Rate | TOTAL |
|---------------|--|------|------|------|-------|
| A | BUSHCLEARING | | | | - |
| | Supply of skilled services for the following works | | | | |
| H3. | BUSH CLEARING | | | | |
| | To be carried out in three phases in accordance with TRMSCAAC latest revision, ESKASABG3 and the Environmental Management Plan, including chemical treatment to prevent regrowth, de-stumping, cutting of felled trees into manageable sizes and stacking on servitude/road edge. (BUSH CLEARING, INCLUDING SUGAR CANE, CROPS AND TREES WITH TRUNKS NOT EXCEEDING 100MM DIA) | | | | |
| H3.1 | Phase 1 | | | | |
| H3.1.1 | Clearance of max. 8m wide strip along centre of servitude as per ESKASABG3 (refer to clause 4.3) | km | 750 | | - |
| H3.1.2 | Clearance around tower sites and guys as per ESKASABG3 (refer to clause 4.3) - per tower | No. | 6000 | | - |
| H3.1.3 | Selective trimming or cutting down of indigenous vegetation outside the 8m strip (item 3.1)(refer to clause 4.3) | km | 2300 | | - |
| H3.1.4 | Clearance of alien species within the servitude as per ESKASABG3 (refer to clause 4.3) | km | 2200 | | - |
| H3.1.5 | Felling of small trees (with trunks exceeding 100mm dia. not exceeding 400mm dia.) | No. | 5750 | | - |
| H3.1.6 | Felling of medium trees (with trunks exceeding 400mm dia. not exceeding 800mm dia.) | No. | 3600 | | - |
| H3.1.7 | Felling of large trees (with trunks exceeding 800mm dia. not exceeding 1200mm dia.) | No. | 480 | | - |
| H3.1.8 | Felling of extra large trees (with trunks exceeding 1200mm dia. not exceeding 1600mm dia.) | No. | 280 | | - |
| H3.2 | Phase 2: (before take-over) | | | | - |
| H3.2.1 | Clearance of max. 8m wide strip along centre of servitude as per ESKASABG3 (refer to clause 4.3) | km | 900 | | - |
| H3.2.2 | Clearance around tower sites and guys as per ESKASABG3 (refer to clause 4.3) | No. | 2600 | | - |
| H3.2.3 | Selective trimming or cutting down of indigenous vegetation outside the 8m strip (item 3.1)(refer to clause 4.3) | km | 3350 | | - |
| H3.2.4 | Clearance of alien species within the servitude as per ESKASABG3 (refer to clause 4.3) | km | 2820 | | - |
| | | | | | |
| | | | | | |
| | | | | | |

FOR ERI:

BOQ Compiled by:

Name: Segametsi Ramoshaba

Job Title: Snr Quantity Surveyor

Signature: 

BOQ Compilation supported By

Name: Ayanda Christian

Job Title: Project Manager (Acting)

Signature: 

FOR SERVICE PROVIDER:

Pricing Done By:

Name: _____

Job Title: _____

Signature: _____

Pricing Approved By

Name: _____

Job Title: _____

Signature: _____