	Scope of Work	Technology
---	----------------------	-------------------

Title: **Upington Strengthening Phase 2 Project: Primary Plant Scope of Work at Ferrum Substation**

Unique Identifier:

Fer21P11-SE-D90

Alternative Reference Number:

N/A

Area of Applicability:

Engineering

Documentation Type:

Report

Revision:

1

Total Pages:

3


Next Review Date:

N/A

Disclosure Classification:

**CONTROLLED
DISCLOSURE**


Compiled by



**Mark Peffer
Engineer
Substation Engineering**

Date: 9/10/2023


Functional Responsibility



**Sipho Zulu
Chief Engineer
Substation Engineering**

Date: 9/10/2023

Authorised by



**Benny Tladi
Middle Manager
Substation Engineering**

Date: 9/10/2023

1. SCOPE OF WORK

The scope of work for this project includes the civil and electrical work as depicted in project drawings Fer21P11 stated in section 2. The scope for Ferrum Substation, based in the Northern province comprises but may not be limited to the following activities:

For a detailed scope see project specific drawings Fer21P11.

400kV		
Quantity	Bay	Scope of Work
1	Feeder 4	Equip vacant bay with new 400 kV Mot Isolators, Earth switch, Line traps, Surge Arrestors, CVT's, Current Transformers and Circuit Breaker as Uppington 1 bay.
1	All	Stringers, droppers & clamps
1	Common Yard	New Foundations, Steelwork and Trenching as required

2. LIST OF DRAWINGS FOR UPINGTON SUBSTATION

Note that the drawings listed below are “NOT FOR CONSTRUCTION” drawings. The successful contractor will order equipment as per specification and supply Eskom with these outlines in order to amend the drawings and issue them “FOR CONSTRUCTION”. Eskom will require at least 60 days from receiving outlines to issuing for construction.

No.	Drawing Title	Drawing Number
1.	Station Electric Diagram	Fer21P11-SE-D6
2.	Key Plan	Fer21P11-SE-D7
3.	Foundation and Trench layout	Fer21P11-SE-D8
4.	Steelwork Marking Plan	Fer21P11-SE-D13
5.	Bay layouts (Sheets 1, 1A, 1B)	Fer21P11-SE-D16

3. AUTHORISATION

This document has been seen and accepted by:

Name	Designation
S Zulu	Chief Engineer
B Tladi	Substation Engineering – Middle Manager

4. REVISIONS

Date	Rev.	Compiler/s	Remarks
October 2023	1	M Pepper	First Issue

CONTROLLED DISCLOSURE

When downloaded from the EDS database, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the Authorized Version on the database.