

	OHS REQUIREMENTS FOR SOLAR PV LETHABO 75 MW PROJECT	Group Capital
---	--	---------------

Title: OHS REQUIREMENTS FOR OHS
REQUIREMENTS FOR SOLAR PV
LETHABO 75 MW PROJECT.

Document Identifier: 375-172744

Revision 1

Compiled by	Supported by	Reviewed & Accepted by	Authorized by
			
Trulley Mabuza Snr Advisor: OHS Gc Gx Coal and Clean	Althea Stuart Middle Manager: SHEQ Gc Gx Coal and Clean	Kanya Kutu Manager Discipline Contract	L Limba Project Manager
Date: 18/09/2023	Date: 18/09/2023	Date: 18/09/2023	Date:

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

Content

	Page
1. Introduction.....	5
2. Supporting Clauses	6
2.1 Scope.....	6
2.3 Purpose.....	7
2.4 Applicability	7
2.5 Effective date	7
3. Normative/Informative References.....	7
3.1 Normative.....	7
3.2 Informative	8
4. Definitions.....	9
5. Abbreviations.....	11
6. Roles and Responsibilities.....	12
6.1 Commitment to OHS	12
6.2 Designers.....	12
6.3 Management and Supervision of Construction Work	13
6.4 Construction Health and Safety Agent, Manager/s and Officer/s	14
6.5 General duties of manufactures and others regarding articles and substances for use at work	14
7. Process for Monitoring.....	15
7.1 Related/Supporting Documents.....	15
7.2 OHS Accountabilities and Responsibilities Organogram incl. the OHS Functional Department Resource Plan	15
7.3 Appointment of Contractors.....	16
8. SHE/Q Policy.....	16
9. OHS Requirements	17
10. Safety Plan and File	18
11. Compliance and Non-Conformances	18
12. Enforcement of OHS Requirements and Non-compliance	19
13. Hazardous Work by Children (Child Labour).....	19
14. Cost allocation for OHS Compliance.....	20
15. Training	20
16. Access and Security Control.....	20
17. Workplace protective measures to be taken during the COVID-19 outbreak.....	21

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

18. Fire Safety Plan.....	21
19. Emergency Preparedness and Response Plan.....	22
19.1 Emergency Response	22
20. Traffic Management Plan.....	22
21. Contractor's Site Facilities	23
22. Public Safety	23
23. Project and Site Rules (Zero Harm to People and the Environment).....	24
24. Hazard Identification and Risk Assessment	27
25. High Risk Activities	30
26. Pre-Task Risk Assessment (DSTI)	32
27. Method Statement, Safe Work Procedures and Practices	32
28. Planned Task Observations (PTO)	32
29. General Walk-downs (Visible Felt Leadership)	33
30. Health and Safety Behaviour Observations and Inspections.....	33
32. Occupational Health and Hygiene	33
32.1 Occupational Hygiene Management Program	34
32.2 Employee Health and Wellness Programme	34
32.3 Medical Surveillance Programme	35
32.4 Medical Services and Medical Emergencies.....	35
32.5 Compensation of Occupational Injuries and Diseases Act (COIDA)	36
33. Forums for OHS Governance and Communication.....	36
34. Permit to Work.....	36
35. Confined Space Work.....	37
36. Management of Pressure Equipment.....	37
37. OHS Audits.....	38
38. Contractor OHS Performance Evaluation	38
39. Documentation and Records Management.....	38
40. Incident Investigation	38
41. OHS Performance Status Reports	38
42. Omissions of this OHS Requirements.....	39
43. Hours of Work	39
44. Night Work.....	39
45. Employees' right of refusal to work in an unsafe situation	39

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

46. OHS requirements for battery energy storage systems, integration equipment, PV Plant and associated projects during operation and maintenance	40
47. Annexure A: The Client's Occupational Health & Safety Requirements	41
48. Annexure B: Eskom SHEQ Policy:.....	47
49. Annexure C: Acknowledgement Form for Eskom OHS Rules & Other Legislative Requirements:	48
50. Annexure D: Emergency Services contact details around Upington (NC):	49
51. Emergency Services contact details around Lethabo PV(Free State):	49

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

1. Introduction

The Occupational Health and Safety (OHS) requirements referred to in this document are Eskom's minimum requirements and should not be construed as all encompassing. The Design, Supply and Installation (DS&I) Contractor is expected to use these (incl. applicable OHS statutory) requirements, referred to in this document, to build into their OHS management system for the project and to consider it when developing the Project OHS Specification, which will be used in the appointment of their Contractors. Eskom in no way assumes the Contractors legal responsibilities.

The DS&I Contractor as a legal entity, and therefore, an employer in their own right (in terms of Section 37(2) of the OHS Act 85 of 1993 (OHS Act), is and remains accountable for the quality and the execution of the safety, health and environmental program for their employees and contractor employees on this project.

Due to the nature and scope of this contract and role and responsibilities that the DS&I Contractor shall be fulfilling, it is to be noted that the duties of the client as referred to in the Construction Regulations 2014 (CR5) of the OHS Act, shall also be fulfilled and complied with in addition to the other applicable statutory OHS requirements. It also must be noted that Eskom as the client still ultimately remains accountable and the DS&I Contractor being responsible & therefore the client reserves the right to be provided with assurance by the DS&I contractor and will conduct its own independent assurance through various mechanisms.

The DS&I Contractor is expected to appoint a competent person in writing as a "Construction Health and Safety Agent" as per the requirement of Construction Regulations 5(5) of the OHS Act, the appointed person must be registered with the approved statutory body, South African Council for the Project & Construction Management Professions (SACPCMP).

It is internationally accepted that some technologies develop faster than health and safety precautions can keep trend with. The expectation is that the DS&I contractor must stay abreast of the latest health and safety developments related to the Distributed battery energy storage system (BESS) and PV Plant being installed, both from a construction and installed technology perspective.

Eskom expectation is that the DS&I Contractor demonstrates & ensures that is committed to achieving and demonstrating sound Occupational Health and Safety (OHS) management by mitigating OHS risks consistent with its OHS management system and objectives on the Distributed battery energy storage systems, networking integration equipment, PV Plant and associated Projects

Zero harm is one of ESKOM values. The aim of Eskom's adoption of Zero Harm as one of its values is to strive to, and achieve world class safety, health and environmental performance, where all Guardians (employees and contractors) return home safely every day and without harm done to the environment we operate in.

The OHS requirements shall be included with the bidding enquiry documentation to the DS&I Contractor, to ensure that the bidder is timeously made aware of:

- Eskom's requirements, including

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

- Eskom's compliance obligations (including Funders OHS Requirements)
- Information that might affect the health and safety of any person at work whether directly or indirectly;
- Activities that may have an impact on the direct and surrounding environment.

The DS&I Contractor is expected to provide an OHS programme based on the requirements of this document, a detailed plan on how they would fulfil the role of a Client in terms of the Construction Regulations 2014(in terms of CR5) and of the applicable OHS statutory requirements for the contracted scope of work as well as provide a draft Project OHS Specification (in terms of CR5 (1)(b)) for the proposed scope of work which meets these requirements as well as the relevant applicable OHS legislation.

When there is an amendment to the Acts and/or to the regulations, an OHS plan must be reviewed, updated accordingly and changes must be communicated to all relevant employees.

2. Supporting Clauses

2.1 Scope

These requirements set out Eskom's expectations regarding the minimum OHS statutory and Eskom requirements for Contractors appointed for the Design, Supply & Installation of SOLAR PV LETHABO 75 MW PROJECT in the Free State.

2.2 Project and Scope of Work Details

Location: Please refer to the Project scope of work in the Free State.

Project description/detailed scope of work: Please refer to the Project scope of work.

Program details:

- Submission of final OHS Plan by Contractors to the DS&I Contractor must be 1 month before site establishment/access to site.
- Construction Work Permit as per the requirement of the Construction Regulations, CR 3(1).
- Notification of construction work as per the requirement of the CR 4(1)

Upon completion of works, the necessary rehabilitation of the site shall be done.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

2.3 Purpose

To provide the Design, Supply and Installation (DS&I) Contractor with Eskom's minimum requirements that they can respond and provide relevant OHS bidding documents which will be assessed by the Client (Eskom) in order to determine if the DS&I contractor company is competent in respect to OHS planning & management on Distributed battery energy storage systems, networking integration equipment, Capacitor banks, PV Plant and associated Projects for Lethabo PV in the Free State.

2.4 Applicability

These requirements are applicable to the Contractor, herein referred to as the DS&I Contractor, appointed for the design, supply & installation of Distributed battery energy storage systems, networking integration equipment, Capacitor banks, PV Plant and associated Projects for Lethabo PV in the Free State.

2.5 Effective date

These requirements shall be implemented from date of approval.

3. Normative/Informative References

Parties using this document shall apply the most recent edition of the documents listed below.

Note: Where the date for revision of a document on the Eskom Document Centre website has passed, the document is still current, irrespective of its revision date having passed.

3.1 Normative

- [1] 32-727: Safety, Health, Environment and Quality Policy
- [2] 240-62196227: Life-saving Rules Standard
- [3] 32-95 Eskom Occupational Health and Safety Incident Management procedure
- [4] Occupational Health and Safety Act and Regulations No 85 of 1993 and its Regulations
- [5] Construction Regulations of 2014 or latest edition as per government gazette.
- [6] Hazardous Substances Chemical Substances Regulations of the OHSACT Act 85 of 1993
- [7] The Constitution of the Republic of South Africa (particularly Section 24 of the Bill of Rights)
- [8] Civil and Building Work Act
- [9] Compensation for Occupational Injuries and Diseases Act

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

- [10] National Road Traffic Act, 1996 (Act No. 93 of 1996)
- [11] 32-37 Substance Abuse Procedure
- [12] All relevant South African legislation (national, provincial, and local)
- [13] Applicable South African National Standards (SANS) for the scope of work/Project.
- [14] 240-54937439: Fire Protection/Detection Assessment Standard.
- [15] 32-124: Eskom Fire Risk Management
- [16] 32-123: Emergency Planning
- [17] 32-1126 Eskom Smoking Policy
- [18] 32-1134 Access Control at Eskom Premises
- [19] 240-56296995 Standard for Record Retention Periods
- [20] Eskom Operating Regulations for High Voltage Systems
- [21] Eskom Plant Safety Regulations (Low Voltage Regulations)
- [22] All relevant COVID 19- Directives and Standards.
- [23] Basic Conditions of Employment Act No 75 of 1997
- [24] 32-136 Contractor Health and Safety Requirements
- [25] 32-520 Risk Assessment procedure

3.2 Informative

Note: The following is a list of documents that can be used as a guide in order to meet legal and Eskom requirements

- [1] 240-129666464 - Group Capital SHEQ related Key Performance Areas, Key Performance Indicators and targets.
- [2] The Vehicle and Driver Safety Management Procedure (240-62946386)
- [3] 32-345 Eskom Vehicle Safety Specification.
- [4] 240-43848327 Employees' right of refusal to work in an unsafe situation
- [5] 32-418: Working from Heights Procedure
- [6] 240-100979499: Personal Protective Equipment for work at Heights Specification
- [7] 32-520: Procedure Manual for Performing Occupational Health and Safety Management and Environmental Management: Conducting EH&S Risk Assessment
- [8] 32-407 Behaviour Safety Observation Procedure
- [9] 39-98: Safe use of Lifting Machines
- [10] 240-43921084- Fall arrester checklist

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

- [11]ISO 45001:2018, Occupational Health and Safety Management Systems-Requirements (Contractor shall use as guideline)
- [12]240-155318598 Workplace Protective measures to be taken during the COVID-19 outbreak for GCD Workplaces
- [13]Tobacco Products Control Act 83 of 1993
- [14]SANS 1186 Symbolic Safety Signs
- [15]DMN 34-110 Operating A Vehicle Mounted Crane
- [16]DMN 34-1981 Excavations.

All contractors are required to execute their works in accordance with these documents as well as other applicable legal documents.

4. Definitions

Baseline risk assessment: baseline operational risks refer to the health and safety risks associated with all standard processes and routine activities in the business.

Client: any person for whom construction work is being performed.

Competent Person: means a person who has in respect of the work or task to be performed the required knowledge, training and experience and, where applicable, qualifications, specific to that work or task: Provided that where appropriate qualifications and training are registered in terms of the provisions of the National Qualification Framework Act, 2000 (Act No.67 of 2000), those qualifications and that training must be regarded as the required qualifications and training; and is familiar with the Act and with the applicable regulations made under the Act;

Construction Health and Safety Agent (CHSA): means a competent person who acts as a representative for a client as per the Construction Regulations (CR) of the Occupational Health & Safety Act, No.85 of 1993, CR 5 (6) (7) and the South African Council for the Project and Construction Management Professions (SACPCMP).

Construction Manager: means a competent person responsible for the management of the physical construction processes and the co-ordination, administration and management of resources on a construction site.

Construction site: means a work place where construction work is being performed

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

Construction Work: means any work in connection with:

- The construction, erection, alteration, renovation, repair, demolition or dismantling of, or addition to, Building or any similar structure.
- The construction, erection, maintenance, demolition or dismantling of any bridge, dam, canal, road, railway, runaway, sewer or water reticulation system, or the moving of earth, clearing of land, the making of excavation, piling or any similar civil engineering structure or type of work.

Contract: is an agreement with conditions between the Client and a DS&I Contractor &/or DS&I contractor and Contractor where an adjudication authority has approved a scope of work to be completed in a specific time frame and within a specified value.

Contractor: These are companies (e.g. suppliers, Principal Contractors, sub-contractors, consultants (all tiers) and consultants etc.) that are contracted by the DS&I Contractor in relation to the project scope. This excludes the DS&I Contractor.

Designer: means any of the following persons:

A competent person who:

- Person who prepares a design
- Person who checks and approves a design
- Person who arranges for any person at work under his/her control to prepare a design, including an employee of that person where he or she is the employer, or designs temporary work, including its components,
- An architect or engineer contributing to, or having overall responsibility for, the design
- A Building services engineer designing details for fixed plant
- A Surveyor specifying articles or drawing up specifications
- A Contractor carrying out design work as part of a design and building project, or an interior designer, shop-fitter or landscape architect.

DS&I Contractor: means a competent organisation who acts as a representative for a client (in this case, this refers to the contractor contracted for the scope of the Design, Supply and Installation. This will also include the legal responsibilities as per CR 5(6) as well as all other applicable health and safety legal requirements related to the project scope.)

Hazard: means a source of, or exposure to danger

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

Medical surveillance: means a planned programme or periodic examination (which may include clinical examinations, biological monitoring, or medical tests) of employees by an occupational health practitioner or, in prescribed cases, by an occupational medicine practitioner

Method Statement: is a written document detailing work procedures and sequences of operations.

Occupational Health and Safety file: means a file or other record in permanent form, containing the information on the OHS management system during construction including all information relating to construction phase after the handover to Client.

OHS Plan: means a site, activity or project specific documented plan in accordance with the client's /DS&I Contractor health and safety specification.

OHS Specifications: means a site, activity or project specific documented prepared by the client/ DS&I Contractor pertaining to all health and safety requirements related to construction work.

On Site/ Site: Any workplace where the contractor or his employees performs contract related work.

Planned Task Observation: is an independent observation made during the planned period in which the task is being executed.

Pre-Task Risk Assessment (DSTI): a meeting which is held prior to the commencement of the day's work with all relevant personnel associated with the work task in attendance.

Safe Work Procedures: Safe work procedures are a series of specific steps that guide a worker through a task from start to finish in a chronological order. Safe work procedures are designed to reduce the risk by minimizing potential exposure.

5. Abbreviations

Abbreviation	Explanation
CHSA	Construction Health and Safety Agent
COID Act	Compensation for Occupational Injuries and Diseases Act
CR	Construction Regulations 2014
DOL	Department of Labour
DS&I	Design Supply and Install
DSTI	Daily Safety Task Instruction
GCE	Group Chief Executive
HCS	Hazardous Chemical Substances
HIRA	Hazard identification and risk assessment
HV	High Voltage
ISO	International Organisation for Standards
JSA	Job Safety Analysis
LTIR	Lost Time Incident Rate
LV	Low Voltage

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

Abbreviation	Explanation
M&O	Maintenance and Operating
MSDS	Material Safety Data Sheet
NQF	National Qualifications Framework
OHNP	Occupational Health Nursing Practitioner
OHS Act	Occupational Health and Safety Act No. 83 of 1993
OHS	Occupational Health and Safety
ORHVS	Operating Regulations for High Voltage Systems
PCS	Power Conversion System
PTO	Planned Task Observations
PV	Photovoltaic
SACPCMP	South African Council for the Project & Construction Management Professions
SANS	South African National Standards
SAQA	South African Qualifications Authority.
SDS	Safety Data Sheet
SHE	Safety, health, and environment

6. Roles and Responsibilities

6.1 Commitment to OHS

Visible and felt Leadership commitment is essential in providing a healthy and safe work environment, Leadership from all stakeholders (Client, DS&I Contractor, Contractors, etc.). Leadership must provide strategic direction and demonstrate commitment in terms of OHS issues both on strategic level and operational level. This must be done by being proactively involved in the day to day operations; in particular OHS aspects of any project / contract. Employees also are expected to demonstrate their commitment. Legislation and the Eskom requirements require that each employee must take reasonable care of themselves and their fellow workers.

6.2 Designers

Designers should ensure compliance with the Occupational Health and Safety Act in terms of Construction Regulations of 2014, Regulations 6 and all other applicable Regulations, standards and legislations.

The designer shall take into consideration & make inputs into the health and safety specification submitted by the DS&I Contractor. (The designer shall then submit to the DS&I Contractor the receipt of acknowledgement of & documented feedback on the health and safety specification document. This shall serve as proof that the designer has taken the H&S requirements into consideration during the design stage and has made inputs).

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

The designer shall take into account the hazards associated with the current constructability as well as future maintenance of the designed structure (s), and make provision in the design(s) for the necessary maintenance work to be performed such that the associated risks are minimised.

They should describe any matters that require particular attention by a contractor. Enough information should be provided to alert contractors and others to matters which they could not be reasonably expected to know about and this will include inherent risks which the contractor will need to be aware of.

In cases where overseas designers are utilised, the appointed designers must indicate and submit to the DS&I Contractor the legislative requirements/documentation with which they comply in order to verify whether they meet the South African OHS legislative requirements.

An overseas designer can appoint a local designer to conduct the inspections required by the construction regulations.

Designers must communicate changes with the DS&I Contractor on designs, as well as designs that affect environmental authorisations/approval issued.

Layout maps depicting coordinates, all the activities (site camps, laydown area, workshop areas, access road etc.) and sensitive areas (such as heritage sites, wetlands, rivers, protected fauna and flora etc.)

Final Designs and layout maps must be approved by relevant Authorities before the commencement of construction.

6.3 Management and Supervision of Construction Work

The DS&I Contractor shall ensure that the performance of all specified work is managed and supervised in accordance with the requirement of OHS Act CR 8 throughout the contract period.

The Contractor shall ensure that the performance of all specified work is supervised throughout the duration of the Contract by a sufficient number of competent appointed representatives of the Contractor, who have experience in the type of work specified.

No work shall commence and/or continue without the presence of an appointed competent Construction Manager, Construction Health & Safety Manager &/ Officer, Construction Supervisor or appointed Construction Supervisor Assistant as per Construction Regulation requirements during execution of the work. These supervisors shall be fluent in the language for communications as defined under the Contract.

Construction Managers are required to register as professionals with the SACPCMP.

Construction Health and Safety Professionals are required to register as professionals with the SACPCMP.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

The DS&I Contractor is required to ensure that resourcing is in accordance with Project Plan and Schedule for life of work. An estimation of key activities is required to be identified for the life cycle of the project and resource plan requires aligning accordingly. The number of appointed persons shall be determined by the size and the risk of the project.

6.4 Construction Health and Safety Agent, Manager/s and Officer/s

The DS&I Contractor shall appoint a competent person in writing as a Construction Health and Safety Agent (CHSA) outlining duties in terms of Construction Regulations 2014 of the OHS Act 85 of 1993, the appointed person must be registered with the approved statutory body, SACPCMP.

A CHSA shall manage the health and safety during the Project Life Cycle, including design phase. Attend design meetings and review and evaluate design concepts and advise on health and safety related matters during the design phase on behalf of the DS&I Contractor.

A CHSA shall ensure that the designer is provided with a copy of the OHS Specification provided by the Client/DS&I Contractor and makes inputs, including their own OHS Specification for specialised activity or operation to adequately address their specialised activities and scope of operation, which shall be included with their bidding enquiry documentation.

A CHSA shall ensure that the designer(s) takes into consideration the health and safety requirements as required in terms of the Construction regulation 2014 (CR 6(1)) of the OHSACT 85 of 1993 during the design phase.

Where a Construction Work permit is required as contemplated in the Construction Regulations 3(1) of 2014, the appointed CHSA shall apply for such Construction permit and supply copy to client.

PLEASE NOTE:

The appointed CHSA shall liaise and collaborate with the Client Health and Safety Manager / Representatives at agreed intervals. The intent is to ensure that the legal requirements of this document are met.

The Contractors shall appoint a full-time Construction Health and Safety Manager and/or officers considering the nature, risk and the scope of work being performed in accordance with the requirement of CR 8 (5)(6). The Construction Health and Safety Professionals are required to register as professionals with the SACPCMP

6.5 General duties of manufactures and others regarding articles and substances for use at work

The DS&I Contractor shall ensure compliance with Section 10 of the OHS Act 85 of 1993.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

The DS&I Contractor shall ensure that the Client (Eskom) is informed of any known or anticipated dangers and hazards relating to any component), networking integration equipment, PV Plant and associated Projects during construction, operating, maintenance and in the event of any emergency situation, to ensure safe operating procedures are followed.

The DS&I Contractor shall ensure that training is provided on any emergency actions for various applicable scenarios in case of an incident involving the distributed battery energy storage system. At a minimum this training shall be made available to affected staff of the Client and where possible the Local Authority Emergency services.

7. Process for Monitoring

This document is valid for the duration of the works and will be amended, as and when necessary, as requirements are being amended and therefore it will be required for the DS&I Contractor and contractor's plan to be amended accordingly.

Conformance to this document shall be via regular safety inspections, audits and any other interventions.

7.1 Related/Supporting Documents

A section 37(2) agreement must be signed between the Client and the DS&I Contractor at the time of awarding the contract. A signed copy of this agreement is submitted to the Client prior to commencement of any activities on site. (Employer's document number 240-59678141).

Acknowledgement Form for Eskom OHS Rules and other requirements (32-726)

Annexure A – Client OHS requirements

Annexure B -SHEQ Policy 32-727

Annexure C- Acknowledgement form for Eskom OHS Rules and other legislative requirements:

Annexure D: Emergency Services contact details around Lethabo PV(Free State):

7.2 OHS Accountabilities and Responsibilities Organogram incl. the OHS Functional Department Resource Plan

The DS&I Contractor shall provide an organisational organogram related to this project, listing all the levels of responsibility from the Chief Executive down to the supervisors responsible for the project. The diagram must list the names of appointees and their roles and responsibilities.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

Provide a proposed OHS resource plan. For each position, stipulate the position titles, qualifications and competencies.

For the duration of the contract, the DS&I Contractor shall ensure that competent persons are appointed in writing in terms of the requirements of the OHS Act 85 of 1993 and its Regulations; and or other statutory requirements and that all their appointees are made aware of their accountabilities and responsibilities and have been suitably trained in terms of their appointment, and advice and assist these appointees in the execution of their duties.

Copies of all the appointments shall be kept in the OHS File during the project duration. All organograms shall be updated timeously when appointments are changed and filed in the project OHS file.

7.3 Appointment of Contractors

The DS&I Contractor may appoint contractors to assist in the contract. All appointments shall be done in writing. The appointed Contractors shall after having considered the size of the project, the degree of danger likely to be encountered or the accumulation of hazards and risks on the site, appoint full-time construction health and safety officers and managers. Registration with SACPCMP is mandatory.

The Contractor involved in Construction Work shall comply with the requirement stipulated in the Construction Regulations 2014 of the OHS Act 85 of 1993, including all the other applicable statutory requirements for their contracted scope of work. Adequate training and instruction must be given to the appointees and ensure that all appointed contractors understand their roles and responsibilities.

The DS&I Contractor shall ensure that all their employees and contractors undergo the relevant Eskom induction and company's induction prior to starting the works.

The DS&I Contractor shall when selecting contractors to assist on this project carry out a selection process, and vet potential contractors. Once the selection process is completed, then such contractors shall be appointed in writing for the relevant period as required

8. SHE/Q Policy

The DS&I Contractor and the contractor companies shall each have an Occupational Health and Safety Policy authorised by their Chief Executive (OHS Act Section 16(1) appointee) that clearly states overall OHS objectives and commitment to improving Occupational Health and Safety performance and must be displayed and shared with all stakeholders.

Eskom has a SHEQ Policy that clearly states the policy principles by which Eskom operates and the commitment to SHEQ excellence and is authorised by the Eskom Group Chief Executive. (See Annexure C

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

9. OHS Requirements

Due to the nature and scope of this contract and role and responsibilities that the DS&I Contractor shall be fulfilling, it is to be noted that the duties of the client as referred to in the **Construction Regulations 2014 (CR5) of the OHS Act**, shall also be fulfilled and complied with in addition to the other applicable statutory OHS requirements. It also must be noted that Eskom as the client still ultimately remains accountable and the DS&I Contractor being responsible & therefore the client reserves the right to be provided with assurance by the DS&I contractor and will conduct its own independent assurance through various mechanisms.

The DS&I Contractor as a legal entity, and therefore, an employer in their own right (in terms of Section 37(2) of the OHS Act 85 of 1993 (OHS Act), is and remains accountable for the quality and the execution of the safety, health and environmental program for their employees and contractor employees on this project.

The Client expects the DS&I Contractor to engage in safety culture initiatives in line with the Eskom SHEQ Policy and value, Zero Harm.

It is required that the DS&I Contractor comply with the relevant applicable legislation, specifications and standards in accordance with the scope of the project.

A section 37(2) agreement must be signed between the Client and the DS&I Contractor at the time of awarding the contract. A signed copy of this agreement is submitted to the Client prior to commencement of any activities.

The DS&I Contractor must ensure that a section 37(2) agreement is signed between them and all their appointed contractors for the contract.

The DS&I Contractor, at all times, considers itself to be the "Employer" for the purposes of the OHS Act, and shall not consider itself under the supervision or management of the Client regarding compliance with the OHS Requirements.

The DS&I Contractor shall furthermore not consider itself to be a subordinate or under the supervision of the Client in respect of these matters. The DS&I Contractor is at all times responsible for the supervision of its employees and contractors and assumes full responsibility and accountability for ensuring they are competent, aware of the OHS Requirements and execute the works in accordance with the OHS Requirements and legislative requirements.

The DS&I Contractor must implement their OHS management system and requirements and incorporate the applicable Eskom requirements into their system.

The DS&I Contractor shall ensure that all statutory appointments and appointments required by the Management system are in place, and that all appointees fully understand their responsibilities and are trained and competent to execute their duties. The DS&I Contractor supervise the execution of their duties by all such appointees.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

The DS&I Contractor is expected to provide an OHS plan based on the requirements of this document, as well as a draft Project OHS Specification (in terms of CR5 (b)) for the proposed scope of work which meets these requirements as well as the relevant applicable legislation.

The DS&I Contractor shall prepare, provide, maintain and update (at defined intervals) a Baseline Project OHS Risk Assessment for the project and communicate to all stakeholders.

The DS&I Contractor shall prepare a suitable, sufficiently documented and coherent site & scope specific safety specification for the intended construction work based on the baseline risk assessment and include the health and safety specification in the tender documents.

The DS&I Contractor shall ensure that the Principal Contractor and contractors comply with the requirements of Construction Regulations 2014, of the OHSACT 85 Of 1993 (including Construction Regulations 7- (Duties of Principal Contractor and Contractor).

The DS&I Contractor shall prepare ensure that each contractors health and safety plan contemplated in regulation 7 (1)(a) is implemented and maintained.

10. Safety Plan and File

The DS&I Contractor shall discuss and negotiate with the Principal Contractor the contents of the Principal Contractor's health and safety plan contemplated in regulation 7 (1)(a) and must thereafter finally approve that plan for implementation.

The appointed CHSA shall liaise and collaborate with the Client Health and Safety Manager / Representatives to ensure that all OHS Obligations are met as per the Construction Regulations.

The Principal Contractor shall ensure that all appointed Contractors (Sub-Contractors) comply with all applicable legislation.

Each Contractor shall provide a Health and safety File for their own scope of work.

11. Compliance and Non-Conformances

As legislation forms part of any country's legal system, the Client requires the DS&I Contractor and all contractors to comply with legislation as part of the contract. All expenses which result from compliance with this legislation as well as special requirements specific to the site will be for the DS&I Contractor account.

Should the DS&I Contractor appoint a contractor, the DS&I Contractor would then have the same role and responsibility in relation to the contractors, in a similar way as the Client has in relation to the DS&I Contractor.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

The Client representative reserves the right to stop work and issue a non-conformance report whenever OHS violations are observed after engaging and making the DS&I Contractor aware of such. Expenses incurred as a result of such work stoppage and standing time shall be for the DS&I Contractor's account. Any non-conformances/findings/observations found in these audits/inspections on contractors shall be raised and discussed with the agent.

The requirements within this document should not be considered to be exhaustive and the Client reserves the right to add, delete or modify conditions where it is considered to be appropriate.

No claim will be accepted as a result of any costs or delays being incurred due to the DS&I Contractor or his contractors not complying with legislation, applicable Eskom Procedures and Standards.

11.1 Legal and Other Requirements

It is the duty of the DS&I Contractor and all contractors to ensure that they are familiar with the necessary OHS legislation required.

The DS&I Contractor shall compile a legal register listing all applicable legislation and standards that may have an impact on the scope of work that they are performing on the construction project. The Client shall have access to the legal register.

The register shall be updated at intervals defined by the DS&I Contractor and where the scope changes including changes in legislations.

12. Enforcement of OHS Requirements and Non-compliance

The DS&I Contractor shall submit their procedure on how they would deal with enforcement and non-compliance to OHS requirements.

13. Hazardous Work by Children (Child Labour)

The constitution of the Republic of South Africa, in the "Bill of Rights" is clear on the rights of children, especially when it comes to:

- a) being protected from exploitative labour practices;
- b) not to be required or permitted to perform work or provide services that
 - are inappropriate for a person of that child's age; or
 - Place at risk the child's well-being, education, physical or mental health or spiritual, moral or social development; and the Basic Conditions of Employment Act, Chapter six Section 43 "Prohibition of employment of children".

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

-
- Before resorting to the use of child labour, due consideration must be given to the rights of the child in terms of the constitution.

Where work is being performed which is not prohibited in terms of the constitution, then such work must be conducted in terms of the OHS Act "Regulations on Hazardous Work by Children in South Africa" with emphasis on paragraph 2 Purpose and Interpretation.

Eskom does not condone the use of child labour and therefore all efforts must be exercised to avoid it.

14. Cost allocation for OHS Compliance

The DS&I Contractor shall ensure that the submitted bid adequately made provision for the cost of all Occupational Health and Safety measures based on the overall contracted scope of the project. (e.g.: resources, medical and emergency services, Covid 19 cost proposal etc).

Please don't limit your response to the above examples provided.

Note: the costing for OHS must be detailed and itemised based on the overall contracted scope of the project.

15. Training

The DS&I Contractor and Contractor need to ensure that the resources to work on the project have the required related training, knowledge and experience specific to the scope of work/services.

The scope of the training includes but is not limited to the type of work being performed and the relevant procedures. In addition to the requirements, the DS&I Contractor and contractor employees would require the appropriate qualifications, certificates and tickets, and be under competent supervision. Records of all training and qualifications of all contractor employees must be kept.

The DS&I Contractor shall maintain comprehensive records of all employees under his control (including all employees of the contractor) attending induction training. Acknowledgement of receiving and understanding the induction must be signed by all persons receiving the induction respectively.

The DS&I Contractor must ensure that the training providers are accredited and registered with SETA according to the relevant unit standards.

The contractor must have proof of this on site for verification.

The DS&I Contractor and its contractors must develop a training matrix for all their employees.

16. Access and Security Control

Access and Security control shall be done according to the Eskom Access Control Policies.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

DS&I Contractor employees, contractors and visitors shall be subjected to induction training and substance abuse tests when entering Eskom sites, or as and when required whilst on Eskom sites.

It may be required that prior to access being granted that person(s) complete the required training e.g. plant access training, employee training, occupational health and safety training or any other prescribed training.

The following are prohibited items and shall not be allowed on Eskom sites unless the necessary authorisation for possession has been obtained:

- Firearms and ammunition (exclude Eskom official firearms/ ammunition and firearms/ ammunition issued to the South African Security Forces)
- Liquor/ Alcohol
- Dangerous weapons
- Drugs
- Any other items that may be declared prohibited

The DS&I Contractor shall ensure that all appointed security personnel and services complies with the applicable South African legislation and Eskom standards and procedures.

The DS&I Contractor and contractor shall provide suitable safety signs, including traffic routes signage's (traffic & pedestrian arrangement) & warning notices/ signs to indicate restrictions or prohibited items, where authorisation is to be obtained.

The DS&I Contractor should develop and implement a sound site security plan as part of their OHS Plan and File.

17. Workplace protective measures to be taken during the COVID-19

The DS&I Contractor and contractor shall ensure that measures required by the applicable latest COVID-19 directives, guidelines and work instructions are strictly complied with.

18. Fire Safety Plan

The DS&I Contractor shall develop and implement an adequate fire safety plan to ensure the overall fire safety, fire prevention and fire protection measures, deemed suitable and necessary for the PV Plant and associated Projects.

All battery types have a tailored auxiliary system for heating, ventilation and air conditioning (HVAC), furthermore, there are enclosures, fire suppression systems and site controllers.

The DS&I Contractor shall enforce the principles of fire safety both on and off the site.

Contractor shall ensure the compliance of fire detection and addressable type alarm system as per relevant standards and regulations. The installation shall meet all applicable statutory requirements

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

and safety regulations of provincial/central fire department/body or any other competent authority in terms of fire protection.

19. Emergency Preparedness and Response Plan

The DS&I Contractor shall, in consultation with the Client regarding the Client's site specific emergency preparedness plan, develop and implement an emergency preparedness and response plan to ensure an adequate level of preparedness, response and recovery for the Distributed battery energy storage system, networking integration equipment, PV Plant and associated Projects, to minimise the impact of an emergency situation pertaining to human life, the environment, security and property.

The DS&I Contractor shall enforce the principles of emergency preparedness both on and off the site.

The DS&I Contractor shall provide training on the approved plan to all the applicable stakeholders.

19.1 Emergency Response

Based on the capabilities of Local Authority Emergency Services, the DS&I Contractor must identify the most appropriate first response actions and minimum safety precautions that first responders must implement during incidents, inclusive of firefighting.

Due to the different approaches by Local Authorities on the provision of fire and emergency services, the DS&I Contractor shall verify the capabilities of the local authority emergency services or such reasonably practicable alternative arrangements to ensure access to fire and emergency response in the event of emergencies.

The DS&I Contractor shall provide a detailed plan as how to access the local authority fire and emergency services or indicate what provision is made for fire and emergency response services and assistance on the project at all times. This shall form part of the DS&I Contractor Health and Safety Plan.

Establish and test the fire and emergency response component of the emergency preparedness plan.

20. Traffic Management Plan

The DS&I Contractor shall develop and implement an adequate traffic management plan, taking into account the safe access and egress of all anticipated traffic, pedestrians and vehicles to all working areas of the site including the core construction area, the lay down areas and site offices. Such traffic safety measures shall include the separation of vehicle and pedestrian traffic to prevent injuries. All vehicles shall be operated by competent and authorized personnel

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

The DS&I Contractor shall enforce the principles of road safety both on and off the site. This shall include the control of vehicles on site, road worthiness, vehicle maintenance programmes, signage, speed limits, flagmen, warning lights and high-level flags if required.

Where access roads pass underneath overhead power lines, the DS&I Contractor shall provide suitable height limitation barriers (goalposts) as agreed upon with the Client.

The DS&I Contractor where applicable shall be responsible for all permits and licences applicable for the project as per the scope of work.

The DS&I Contractor shall ensure that maintenance of the roads under his supervision are maintained, managed by the Principal Contractors and Contractors and that all Traffic Management plans of Principal Contractors are approved.

Contractor's Site Facilities

Site facilities shall be established and maintained by the DS&I Contractor. The facilities include, but are not limited to the following: (refer to OHS Act Construction Regulation 30)

- Temporary Facility Layout Plan
- Sheltered eating facilities
- Change rooms
- Ablution facilities
- Site Sheds, Offices and Amenities
- Contractor Site Camps
- Lay down and Storage
- Temporary Site Services(Alternative sites)
- Rehabilitation of the site once completed

Reasonable and suitable living accommodation may be provided for employees who are far removed from their homes and where adequate transportation between the site and their homes, or other suitable living accommodation, is not available

21. Public Safety

Legislation requires that employers shall be responsible, as far as reasonably practicable, for safeguarding persons other than those in their employment who may be directly affected by their activities so that they are not exposed to hazards to their health and safety (Section 9 of the OHS Act).

The DS&I Contractor and Contractors shall factor in, in their safety plan, how they intend safeguarding/ controlling any members of the public against their activities during the project.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

The DS&I Contractor shall consider community Public Safety interventions and awareness programmes to ensure that personnel or members of public are safe from operations and activities. The DS&I Contractor and Contractors shall ensure that the site under their supervision is adequately fenced off and maintained.

22. Project and Site Rules (Zero Harm to People and the Environment)

The objective of this section is to define the rules that are over and above the internal regulations and procedures of Eskom and relevant legislation which will ensure zero harm to persons and the environment. These rules will be specific to the project and site.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

Eskom Life Saving Rules

Five Life Saving rules have been developed that will apply to all DS&I Contractor employees, Agents, consultants, contractors and visitors. Failure to adhere to these rules will be considered a serious transgression. These rules are being implemented to prevent serious injury or death of any employee, labour broker or contractor working in any area within Eskom.

The rules are:

RULE	DESCRIPTION OF RULE
Rule 1	OPEN, ISOLATE, TEST, EARTH, BOND, AND/OR INSULATE BEFORE TOUCH (That is plant, any plant operating above 1000 V)
Rule 2	HOOK UP AT HEIGHTS Working at height is defined as any work performed above a stable work surface or where a person puts himself/herself in a position where he/she exposes himself/herself to a fall from or into.
Rule 3	BUCKLE UP No person may drive any vehicle on Eskom business and/or on Eskom premises: Unless the driver and all passengers are wearing seat belts.
Rule 4	BE SOBER No person is allowed to be under the influence of intoxicating liquor or drugs while on duty
Rule 5	PERMIT TO WORK Where an authorisation limitation exists, no person shall work without the required permit to work.

Eskom will take a stance of zero tolerance on these rules

Any non-compliance to any health and safety requirement in this OHS specification is subject to discipline/removal of person from the project site.

Non-compliance to a Life Saving rule will be considered serious misconduct and will lead to serious disciplinary action, which may include dismissal.

This is to ensure that every person who works on or visits an Eskom work site returns home safely to his or her family

No person shall damage, alter, remove, render ineffective, or interfere with anything that has been provided for the protection of the site, or for the health and safety of persons.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

No person under the influence of alcohol, drugs or medication (in a state of intoxication) or any other condition that may render him incapable of controlling himself or of other persons under his charge shall be allowed to enter the site.

All safety and warning signs shall be obeyed at all times.

Entering or leaving the Site will only take place at official access control points and may only be done via the official designated walkways.

All employees shall adhere to the OHS and other site-specific rules.

The DS&I Contractor must have a process in place to address employees that have contravened Health and Safety Requirements.

- **Smoking**

Smoking is only permitted at designated areas in accordance with the requirements of the smoking policy (32-1126: Eskom Smoking Policy).

- **Cellular Phones**

Do not use Cellular phones in areas where cell phone usage is prohibited.

A contractor shall develop and implement a risk-based cell phone policy for a particular construction site.

- **Fire Extinguishers**

All fire extinguishers shall be:

- Clearly labelled
- Conspicuously numbered
- Entered in a register
- Inspected monthly by a competent person
- Tested and serviced at recommended intervals by an accredited supplier
- Results shall be entered in the register and signed by competent person.
- No open or unattended fires are allowed within the construction site.

DS&I Contractor shall have a layout plan of a site indicating where all his firefighting equipment is located.

- **Vehicles and Traffic Rules**

Ensure that all drivers and passengers wear seatbelts, where fitted, while travelling in a motor vehicle. Vehicles not fitted with seatbelts must be retrofitted according to the vehicle manufacturer's specifications.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

Ensure that no employees, including contractor employees, when performing work for Eskom, are transported at the back of bakkies / vans and trucks.

- **Substance and Drug Abuse Management**

The DS&I Contractor shall provide a **Substance Abuse management plan** which is in line with the Eskom Procedure (Eskom Substance Abuse Procedure 32-37)

Alcohol and substance abuse pose a significant threat to any business, more so in industrial incidents and the driving of vehicles. Eskom is therefore, entitled to take reasonable steps to ensure that intoxicated persons are identified and prevented from entering Eskom.

General Safety Regulation 2A is clear on the legal stance regarding intoxication.

The DS&I Contractor shall implement a **zero tolerance** to substance abuse

All contractors shall comply with Eskom's procedure 32-37 ("Substance Abuse Procedure"), taking in to account that this is an Eskom Life-saving Rule number 4: BE SOBER", this means anyone entering the Eskom will be subjected to ad hoc alcohol testing.

Contractors are encouraged to compile their own manual and to carry out regular alcohol testing of their own employees. The legislative alcohol level is deemed to be zero.

Test records must be treated as "Confidential" and filed in the employees' personal file.

23. Hazard Identification and Risk Assessment

It is a legal requirement in terms of Section 8 (2)(d) of the OHS Act for an employer to carry out risk assessments, to establish which risks and hazards are attached to the health and safety of persons due to any work which is performed, any article or substance which is, handled, stored, transported.

The DS&I Contractor shall prepare, provide, maintain and update (at defined intervals) a Baseline Project OHS Risk Assessment for the project and communicate to all stakeholders. The Contractors are expected to have different types of risk assessments for their scope of work.

A Risk Assessment process should be aligned with Construction Regulation 9 (1) (a-e). Emerging risks and hazards must be managed during construction work. This means that if there are significant changes to a process or activity, or any new process, then these should also be subjected to risk assessment. All risks must be rated.

Risk assessments shall be conducted by an appointed competent risk assessor. Risk assessment shall be developed by cross-functional team and outcome shall be shared with employees.

Attendance registers must be kept of all the employees involved in compiling the risk assessment

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

HIGH LEVEL OHS RISKS AND SUGGESTED MITIGATING FACTORS (BUT NO LIMITED TO THE FOLLOWING):

The following risks referred to in this document are Eskom's minimum requirements and should not be construed as all-encompassing. This list is to be transferred to the Risk Register that the DS&I Contractor will update and maintain at regular intervals.

RISKS	Suggested Mitigating Factors	Responsible Person
<ul style="list-style-type: none">Non-Compliance to applicable legislations and standards	Compile a legal register listing all applicable legislation and standards that may have an impact on the scope of work. The register shall be updated regularly. Identify all applicable OHS permits related to the scope of work. Apply for the permit with relevant authorities.	DS&I Contractor DS&I Contractor
<ul style="list-style-type: none">Working/interfaces on an existing operational site	Works coordination process to be established with inputs from all affected stakeholders	DS&I Contractor
<ul style="list-style-type: none">Weather ConditionsTemperatures /hot/cold/wind speed and direction	Obtain site data info Rigging activities to consider wind speed and direction including all other high risk activities Manual handling to consider below 0 temperature	Client DS&I Contractor
<ul style="list-style-type: none">Road /Terrace ConditionIncreased Volume in the areaAbnormal loads	Consider all roads inside and outside site in the Traffic Management Plan. -Movements of vehicles, mobile plants and pedestrian on site and surrounding areas.	DS&I Contractor
<ul style="list-style-type: none">Availability of Medical facilities and services	Provide a detailed plan as to how access to or provision of medical facilities, services and assistance is rendered on the project at all times. This shall form part of the DS&I Contractor Health and Safety Plan.	DS&I Contractor

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

	Establish and test an Emergency medical response plan and ensure that it is aligned with emergency response plan	
<ul style="list-style-type: none"> Delivering of construction material. 	To be considered in the Traffic Management plan, taking into account the road conditions.	DS&I Contractor
<ul style="list-style-type: none"> Storage of Hazardous Chemical Substances on site 	Comply with the Hazardous Chemical Substance Regulations of the OHS Act and Major Hazard Installation Regulations (if applicable).	DS&I Contractor
<ul style="list-style-type: none"> Spillages, explosives and fire 	Fire Safety and Emergency Preparedness Plan.	DS&I Contractor
<ul style="list-style-type: none"> Explosive Environment and Fires 	Intrinsically safe equipment- Light fixtures/electrical equipment and ban cell phones usage. Post signage.	DS&I Contractor
<ul style="list-style-type: none"> Loss of containment/ spillages Presence corrosive acid 	<p>Correct Personal Protective equipment for workers in that environment. (I.e. wet suits).</p> <p>Ventilation if the acid or chemical becomes a gas/vapour.</p> <p>Gas detection, extraction Fans/vents.</p> <p>In the event of emergencies- availability of self-contained breathing apparatus (should be risk based)</p>	DS&I Contractor
<ul style="list-style-type: none"> Manual handling of batteries resulting in Muscle sprains/ back pains (musculoskeletal disorders) 	Compliance with the applicable legislation and standards	DS&I Contractor
<ul style="list-style-type: none"> Working underneath/on close proximity of the powerlines 	Comply with the ORHVS Regulations	DS&I Contractor
<ul style="list-style-type: none"> Maintenance and Operational Risks 	Consider Maintenance Risks at design stage.	DS&I Contractor

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

<ul style="list-style-type: none">• All other Risk as per the scope of work	The DS&I Contractor and Contractor to conduct Risk Assessment for their activities	DS&I Contractor
<ul style="list-style-type: none">• Drivers fatigue	Consider rest periods and driver behaviour when driving	DS&I Contractor/client
<ul style="list-style-type: none">• Technology options for the proposed project	The DS&I Contractor and Contractor to conduct Risk Assessment for all the technologies activities	DS&I Contractor
<ul style="list-style-type: none">• Wild animals and document animals	Avoid driving at night or the environment not conducive	DS&I Contractor/client
<ul style="list-style-type: none">• Access control to the working site including cross boarder movement of people and vehicles	Traffic Management plan and restricted access plan	DS&I Contractor/client

24. High Risk Activities

When the DS&I Contractor and/or his contractors are working in an area where a high health and safety hazard exists, the DS&I Contractor shall:

- Ensure that permanent and adequate on-site supervision is available for the entire duration of the work that is being conducted.
- Ensure the use of safety standbys in areas of high-risk activities, and activities that fall within the scope of the permit to work system.
- Provide, erect and maintain all the required barricading, lighting, flags, flashing lights, or other safety control equipment to enable operations to proceed in a safe manner;
- Maintain, at all times, defined access ways, which are clear of objects or obstructions, so as to allow for emergency vehicle entry; and
- Provide any temporary protective shielding required for protecting nearby operations from the construction activities, at their own cost.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

-
- When crossing roads, railway tracks and other power lines during operations, the contractor shall ensure that rugby poles are properly erected at all road crossings and that the public is warned, and flagmen placed at strategic positions to warn traffic/motorists. DS&I Contractor shall ensure that whenever mobile cranes/ lifting machinery are operated onsite, the booms are retracted and safe clearances from overhead power lines, communication lines or other overhead obstructions are observed and maintained as per Electrical Machinery Regulations 19 & 21, Eskom Procedure "Operating Regulations for High Voltage Systems (ORHVS)-32-846" Section 5.03.6.3 (Work in close proximity to live conductors / apparatus). Supervisors shall be trained in the Eskom ORHVS (see above).
 - Height restriction barriers/cross-bars must be erected on both sides of the overhead power lines, communication lines or other overhead obstructions. Establish the permitted safe clearances in consultation with the owner of the line.
 - What are your company's critical success factors, plans, and requirements in managing high risk construction activities such as (if applicable)?
 - Civil works
 - Lifting and rigging
 - Crane Coordinator
 - Blasting
 - Hot work
 - Work at height
 - Stacking and Storage
 - Manual Handling
 - Electrical safety/ Close Proximity to live apparatus
 - Hazardous Chemical Substances
 - Confined Spaces
 - Construction traffic and vehicles etc.
 - Transportation of staff
 - Underground Surveys.
 - Exposure to Physical, biological and chemical stresses
 - Distributed Battery energy storage system.
 - PV Plant installation

NOTE: Please don't limit response to the above list of activities.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

25. Pre-Task Risk Assessment (DSTI)

The Contractor shall on a daily basis and for every task to be performed, conduct a pre-task risk assessment with all employees involved with the task(s). The pre-task risk assessment will form the basis of the daily pre-job brief/toolbox talks prior to the start of work. This will highlight critical steps from the safe work procedure to ensure that work is performed in a safe manner. Proof of communication as well as confirmation that it was received and understood by all will be noted on a standard form, which will be kept at the job site during the job execution. The completed signed pre-task risk assessment form shall be filed in the DS&I Contractor's safety file.

26. Method Statement, Safe Work Procedures and Practices

The DS&I Contractor shall compile project / site specific method statements and safe work procedures for all the high-risk activities as identified in the risk assessment and scope of work. These shall be approved by the DS&I Contractor.

Commencement of any work activity does not take place unless a method statement, risk assessment and safe work procedure has been produced and submitted to the DS&I Contractor (and permission has been received), in advance of any proposed specific activity starting. They must be site and task specific, clear and signed off.

The supervisor / team leader shall ensure that all employees are trained on all applicable safe work procedures. Records of training/ awareness shall be kept on site.

27. Planned Task Observations (PTO)

The DS&I Contractor shall provide the planned task observation procedure or process covering but not limited to the following:

- Persons responsible for monitoring the task and carrying out the Planned Job Observation must be the supervisor;
- Planned job observations should be conducted in such a way that the employee is observed against the actual steps (of the written safe work procedure) to be followed when performing a task and be marked against compliance with each step. This will assist in determining employee competence and compliance. Record should be kept at all times.
- Where the employee did not comply or did not follow the required steps, this should be indicated on the report and actions be taken to correct the deviation.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

28. General Walk-downs (Visible Felt Leadership)

The Senior Managers from the DS&I Contractor and Contractors shall lead the site walk downs with the Construction Supervisors and the management representatives from the DS&I Contractor at agreed intervals to demonstrate their commitment towards OHS matters and Visible Felt leadership. These sites walk downs will be used to identify both strengths and areas for improvement regarding OHS issues. Site Walk downs will be documented, inclusive of an action plan to close out all deviations noted during such a walk-down.

Describe how and what measures are taken by Senior Leadership to actively drive OHS with employees and contractors.

Consider the following Criteria:

- Visibility on sites where operations take place.
- Interventions that leadership drive specifically on OHS matters.
- What monitoring mechanisms are in place to verify the above?

29. Health and Safety Behaviour Observations and Inspections

The objective of behavioural safety observations is to assess and address the actual safe and unsafe behaviours of people in the workplace; as well as workplace conditions - which are caused by the actions or non-actions of employees, contractors or their supervisors.

The DS&I Contractor is expected to describe how their company would implement a behavioural safety programme.

30. Management of Hazardous Chemical Substances

Safety Data Sheets to be obtained for all hazardous chemicals. Copies Safety Data Sheets to be kept on site as to ensure that emergency information is available at all times;

All employees to be trained on the dangers posed by the chemical substances used; and

All employees that uses Hazardous Chemicals to be provided with and are required to wear respiratory protective equipment.

Medical screening of such persons to be done as per OHSA

Storage of Hazardous Chemicals to comply with the OHSACT Regulations

31. Occupational Health and Hygiene

DS&I Contractor is required to develop an Occupational Health and Hygiene program. The program is intended to ensure that the risks to health are identified and controlled.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

31.1 Occupational Hygiene Management Program

DS&I Contractor and contractors shall develop, implement and maintain an occupational hygiene management programme to ensure that the occupational hygiene stressors are identified assessed (monitored) and controlled.

The occupational hygiene should include, but not be limited to the following elements:

- Occupational health risk assessment as a background.
- Occupational health risk exposure profiles
- Occupational hygiene monitoring program and ensure that monitoring is performed by an approved Inspection Authority.
- Communication of occupational hygiene results and requirements
- Proof of awareness training.
- Documentation and control of records (Records to be kept for 40 years)

Where there are occupational hygiene stressors, the contractors shall ensure that programs are developed and in place to address the said stressors. These programs may include but not be limited to:

- Hearing Conservation Program;
- Respiratory Protective Program
- Hazardous Chemical Substances Program
- Procedure for the use and management of radioactive sources
- Heat Stress Management Program

DS&I Contractor and contractors shall report to the Department of Labour and Department of Minerals Resources on the occupational hygiene milestones (e.g. crystalline silica). Evidence of reporting to the department of labour and copies of such reports shall be made available to OHS manager/practitioner.

Copies of all occupational hygiene surveys conducted by the DS&I Contractor and contractor must be submitted to the Eskom OHS manager and practitioners. The DS&I Contractor shall establish a database of occupational hygiene surveys and corrective plans.

The DS&I Contractor and contractors shall describe in detail how they would implement an Occupational Hygiene programme and provide an outline of the programme as well.

31.2 Employee Health and Wellness Programme

The DS&I Contractor shall submit details of their Employee Health and Wellness Programme as part of their Health and Safety Plan which should include a Medical Surveillance Program and an Employee Assistance Program.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

31.3 Medical Surveillance Programme

The DS&I Contractor shall ensure that his employees and contractor employees are registered on a medical surveillance programme and are in possession of a valid medical certificate of fitness. The medical certificate of fitness shall be relevant to the type of work (risk based) that the employee will be exposed to. This will require each employee to have a risk-based person job specification that will be used as a basis for medical examination.

The DS&I Contractor must ensure that his employees and contractor employees have undergone pre-entry medical examination before starting work on site, ***no employee will access site without a valid medical certificate of fitness.***

The DS&I Contractor and contractor employees must ensure that all their employees have a valid medical certificate of fitness specific to the construction work to be performed and issued by an Occupational Health Practitioner in the form of Annexure 3.

The frequency to renew the medical certificate of fitness shall be determined by the risk profile and or as per the recommendation of the Occupational Health Practitioner.

On completion of the project an exit medical examination shall be conducted, unless otherwise advised by the Occupational Health Practitioner.

All employees shall be issued with the required medical records to prove medical status at the time of exiting the construction project.

The DS&I Contractor shall provide a documented process for managing those employees who are issued with a conditional certificate of fitness or restrictions.

Note: *Eskom will only accept medical surveillances conducted by an Occupational Health Practitioner who holds a qualification in occupational health.*

31.4 Medical Services and Medical Emergencies.

Due to the unavailability of Eskom in-house medical facilities in the areas of work, the DS&I Contractor shall investigate alternative arrangements to ensure access to adequate medical assistance in the event of emergencies.

The DS&I Contractor shall provide a detailed plan as to how access to or provision of medical facilities, services and assistance is rendered on the project at all times. This shall form part of the DS&I Contractor Health and Safety Plan

DS&I Contractor and its Contractors will need to develop a plan on how to manage Medical Services and Medical Emergencies.

Establish and test the Emergency medical response component of the emergency preparedness plan.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

31.5 Compensation of Occupational Injuries and Diseases Act (COIDA)

The DS&I Contractor shall submit proof of registration and letter of good standing with the compensation fund or with a licensed compensation insurer for his company; based on South African legislative requirements. This must remain valid for the duration of the contract. The Letter of Good Standing shall reflect the name of the DS&I Contractor. The Contractors are expected to provide the same to the DS&I Contractor.

32. Forums for OHS Governance and Communication

Effective governance and communication structures shall be established on each project site where project OHS matters shall be discussed. Attendance registers and minutes shall be kept for all the health and safety meetings. The terms of reference shall be established for each governance structure on the project.

The DS&I Contractor/s shall provide a communication plan outlining the discussions and decisions to their staff, the mediums they will employ and how they will measure the effectiveness of their OHS communication.

Every meeting conducted on site shall include OHS as a standing agenda point and minutes of these meetings shall be available on site at all times.

NOTE: These meetings do not replace or act as a substitute for the required OHS statutory meetings.

Statutory OHS Committees in terms of Section 19 and 20 and General Administrative Regulations 5 of the OHS Act and Eskom requirements shall be established.

33. Permit to Work

The DS&I Contractor must adhere to the approved & Compulsory Eskom Permit to Work System to control identified high risk activities. There will be only one Permit to Work system (Eskom) on the construction site, as per the legislation and best practises.

The DS&I Contractor together with the appointed contactors on this project shall identify persons to be trained and authorised for the Electrical Permit to work systems. Eskom Regulations indicated below. After training the supervisors will be assessed for competence and authorised in writing to perform the duties of an authorised or responsible person as contemplated in the applicable Eskom regulations e.g.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

- Operating Regulations for High Voltage Systems.
- Plant Safety Regulations.
- Pulverised Fuel firing regulations.
- Hot Work Permits etc.

The Client will provide more details on the permit to work system for the specific work to be conducted by the DS&I Contractor.

34. Confined Space Work

All confined spaces shall be considered "permit-required" spaces unless a pre-entry procedure has demonstrated otherwise. A permit shall be completed before approval can be given to enter a "permit-required" confined space. This permit shall be maintained at the jobsite for the duration of the job.

All confined spaces shall be tested for poisonous gases and/or oxygen deficiency prior to entry.

When in confined areas such as boilers, tanks, drums, manholes, etc., or where noxious or poisonous gases may be present, the appropriate breathing apparatus shall be used.

Where dangerous gases or harmful substances are present in the immediate work area, air-supplied masks shall be worn.

Proper ventilation and all other required protective equipment shall be used.

Hazardous work areas containing noxious or poisonous gases shall not be entered without proper protective equipment being worn and without being accompanied by a fellow employee who has been properly trained and familiar with the use of such protective equipment.

35. Management of Pressure Equipment

The DS&I contractor shall ensure they comply at all times with the requirements of Pressure Equipment Regulations, 2009 with specific reference to the following:

- Ensuring all Equipment owned and hired-in Vessels under pressure, comply with the 36-month pressure vessel inspection, and a certificate of testing is available on site.
- Ensure that all temporary pressure vessels are subjected to a pressure test after they have been installed or moved and reinstalled in a new position.
- Ensuring that all personnel who shall use this equipment are competent and trained.
- Ensure the users of this equipment are issued with the required PPE.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

-
- Ensuring the area is adequately identified as a noise area and warnings are posted.
 - Ensuring daily pre-start inspections are carried out on all the equipment and the findings recorded on the standard inspection register.
 - Ensure the correct fire prevention and fighting equipment is available at all times.
 - Noise levels where possible shall be kept within reasonable operating norms.

36. OHS Audits

Eskom reserves the right to monitor and conduct unannounced audits to ensure compliance and provide assurance to the Client representatives and their key stakeholders.

37. Contractor OHS Performance Evaluation

Eskom shall evaluate contractor OHS performance on an on-going basis against the Eskom requirements.

38. Documentation and Records Management

The DS&I Contractor shall establish and maintain a documentation and records management system where all project and scope OHS related documentation and records are kept and maintained.

The OHS file shall be handed over to the Client (Eskom) at the end of the DS&I Contractor's contract.

The Client shall have access to this system

39. Incident Investigation

The DS&I Contractor and Contractors shall report all incidents/accidents as required in terms of the legislation.

All OHS incident reporting, recording, classification and investigation will be done according to the requirements set out in the Eskom document 32-95 (latest version)

40. OHS Performance Status Reports

The DS&I Contractor and contractors shall provide an OHS Statistical and Non-Statistical Reports, dashboards, presentations as per the Client requirements.

Reporting must not be later than the 3rd of every month.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

41. Omissions of this OHS Requirements

By drawing up these OHS requirements Eskom has endeavoured to address the most critical aspects relating to OHS issues in order to assist the DS&I Contractor in adequately addressing the health and safety management of persons on site.

Should Eskom not have addressed all aspects pertaining to the work that is tendered for, the DS&I Contractor needs to ensure that all applicable OHS requirements are identified and included in their management system, OHS Plan, Draft OHS Specification, policies, standards and procedures.

42. Hours of Work

All work conducted on site shall fall within the legal requirements in accordance with the Basic Conditions of Employment Act and all applicable South African legislations.

The DS&I Contractor shall be aware of the effects of human fatigue and regulate overtime accordingly. The baseline risk assessment must be reviewed to include the management of overtime work.

43. Night Work

When night work is to be performed; the DS&I Contractor shall provide sufficient lighting to enable the entire work site to be illuminated to a degree that employees will not work in dark (un-illuminated) or dimly lit areas. Care must be exercised as not to use few lights with high light intensives as this will cause night blindness.

If work is continuing from day light into night, at dusk, a tool box talk must be held where all employees will be advised of the hazards of night work and the extra precautions which require to be taken, i.e. poor housekeeping, stepping on uneven ground, stepping into holes etc.

44. Employees' right of refusal to work in an unsafe situation

Employees have a duty to take reasonable care of their own as well as other person's health and safety at work and to cooperate with the employer, carry out lawful orders, including reporting unsafe situations and incidents.

Refer to Eskom Procedure 240-43848327- Employees' right of refusal to work in an unsafe situation. The aim of the procedure is to ensure that an environment is created that promotes zero harm by empowering employees and contractors to take responsibility for their own safety and that of others.

The DS&I Contractor shall provide an Employees' right of refusal to work in an unsafe situation procedure which is in line with the Eskom Procedure 240-43848327.

NOTE: Work stoppages that are initiated due to SHE related incidents shall not warrant any financial compensation claim lodged against Eskom.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

45. OHS requirements for battery energy storage systems, integration equipment, Capacitor banks, PV Plant and associated projects during operation and maintenance

The Client expects the DS&I Contractor to ensure the OHS Management scope is adjusted to the phase of operation & maintenance and engage in safety culture initiatives in line with the Eskom SHEQ Policy and value, Zero Harm during the operation and maintenance of the complete plant facility.

It is required that the DS&I Contractor comply with the relevant applicable legislation, specifications and standards in accordance with the scope of the project in all its phases and including execution of the contract.

The DS&I Contractor shall ensure that the Client (Eskom) is informed of any known or anticipated dangers and hazards relating to any component within the Distributed battery energy storage system integration equipment, PV Plant and associated projects during operating, maintenance and in the event of any emergency situation, to ensure safe operating procedures are followed.

The DS&I Contractor shall identify the most appropriate first response actions and minimum safety precautions that first responders must implement during incidents, inclusive of firefighting.

The DS&I Contractor shall ensure that training is provided on any emergency actions for various applicable scenarios in case of an incident involving the distributed battery energy storage system. At a minimum this training shall be made available to affected staff of the Client and where possible the Local Authority Emergency services.

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

46. Annexure A: The Client's Occupational Health & Safety Requirements

The following minimum Occupational Health & Safety related requirements that bidders have to address and respond to when submitting their bidding returnable are as follows:

Ref.	Eskom Health and Safety Requirements Checklist	Proof required	Yes	No	N/A
1	Organisational Structure & Competencies of Key Appointees				
1.1	Provide an OHS resource plan for the proposed scope of work. For each position, stipulate the position titles; roles; responsibilities, accountability, qualifications and competencies that will be required for each position.	✓			
1.2	Please provide CV's of individuals that will fulfil the following roles, plus proof of registration with relevant approved professional body where applicable:	✓			
	• Construction Health and Safety Agent in terms of Construction Regulations 2014, CR 5 (5) (6) and (7) and as per the SACPCMP requirements.	✓			
	• Registered Designer(s).	✓			
	• Construction Health and Safety Manager and Officers in terms of Construction Regulations 2014, CR 8 (5) and (6) and as per the SACPCMP requirements.	✓			
	• Construction Manager in terms of Construction Regulations 2014, CR 8 (1) and as per the SACPCMP requirements.	✓			
	• Construction Supervisor & Assistant Construction Supervisor in terms of Construction Regulations 2014, CR 8 (7) and (8).	✓			

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

Ref.	Eskom Health and Safety Requirements Checklist	Proof required	Yes	No	N/A
2	Occupational Health & Safety Plan and OHS Management System				
	<ul style="list-style-type: none"> Provide in terms of CR 7 (1) (a) Construction Regulations 2014, an OHS plan for the proposed scope of work in response to this OHS Specification/Requirements. 	✓			
	<ul style="list-style-type: none"> Does your Company have a recognised OHS Management System? If yes, please provide a copy of the certification. 	✓			
	<ul style="list-style-type: none"> Provide a copy of a typical Health and Safety risk profile for a project of this nature as well as high level interventions that will be implemented to mitigate the risk. 	✓			
3	Fire Safety and emergency requirements				
	<ul style="list-style-type: none"> Provide baseline emergency risk assessment. 	✓			
	<ul style="list-style-type: none"> Provide Fire Safety, Emergency Preparedness and Response Plan. 	✓			
	<ul style="list-style-type: none"> Provide a detailed plan as to how to access the local authority fire and emergency services or indicate what provision will be made for fire and emergency response services and assistance on the project. 	✓			
	<ul style="list-style-type: none"> Provide a detailed plan as to how you will ensure provision of medical facilities, services and assistance at all times on the project. How will you address medical emergencies? 	✓			

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

Ref.	Eskom Health and Safety Requirements Checklist	Proof required	Yes	No	N/A
4	Legal Requirements				
	<ul style="list-style-type: none"> Provide in terms of CR 5 (b) Construction Regulations 2014, an OHS specification for the proposed scope of work that will be issued to the Contractor's. 	✓			
	<ul style="list-style-type: none"> Explain how you would manage the evaluation and selection process of joint venture or sub-contractors to ensure that they have the necessary competencies and resources to perform the work safely. 	✓			
	<ul style="list-style-type: none"> Provide a signed copy of Annexure C: Acknowledgement Form for Eskom OHS Rules & Other Legislative Requirements: 	✓			
	<ul style="list-style-type: none"> DS&I Contractor to provide a detailed plan how to fulfil the responsibility and accountability in terms of the Construction Regulations 2014, and of the relevant OHS statutory requirements. 	✓			
	<ul style="list-style-type: none"> Explain how you would manage and monitor contractor companies in terms of Health and Safety compliance. 	✓			
	<ul style="list-style-type: none"> Explain how you would manage multiple contractor company interfaces on the project. 	✓			
	<ul style="list-style-type: none"> Provide a detailed costing for OHS on the overall scope of works/services to be performed in the Costing Schedules. 	✓			
	<ul style="list-style-type: none"> Is your company registered with COID or with a licensed compensation insurer based on South African legislative requirements and are you still in good standing? If yes, please provide copy of current valid certificate issued by the Compensation Commissioner. 	✓			

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

Ref.	Eskom Health and Safety Requirements Checklist	Proof required	Yes	No	N/A
5	Occupational Health & Safety Operational Controls				
	OHS Operational Controls What are your company's safe work plans in managing high risk activities that will be applicable to the scope of work on this project? <ul style="list-style-type: none"> Provide documents of any known or anticipated dangers and hazards relating to the Distributed Battery Energy Storage Systems and Capacitor banks, Solar PV during construction, maintenance and operating, and safe operating procedures to be followed. 	✓			
	<ul style="list-style-type: none"> Please provide a process/ procedure on how you would deal with companies/individuals that have transgressed OHS requirements. 	✓			
6	OHS Historical Safety Performance relevant to the scope of work.				
	Please provide details of OHS safety performance relevant to the scope of work.	✓	NM		

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

COMPANY ACKNOWLEDGEMENT

I acknowledge that the information provided in this Occupational Health and Safety Questionnaire, as part of the Eskom OHS evaluation process, is true and correct.

Company name:

Name and surname: Position:

Signature: Date:

FOR OFFICE USE ONLY

Comments:

OHS EVALUATION RESULT (Ring the correct one): Recommended/Not Recommended

NAME OF ASSESSOR:

SIGNATURE:

DATE:

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

Evaluation Criteria:

Description	Rating
Meets Client's Requirements:	2
Partially meet Client's Requirements:	1
Does not meet Client's Requirements:	0

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

47. Annexure B: Eskom SHEQ Policy:

Eskom's Safety, Health, Environment and Quality (SHEQ) Policy Poster (32-727) Rev 6



Eskom will integrate and/or incorporate safety, health, environment, and quality requirements through the plan-do-check-act (PDCA) quality cycle in its activities so that decisions made ensure the consideration of economic development, environmental duty of care, and social equity to improve performance and achieve stakeholder requirements continually.

Eskom's commitment to safety, health, environment and quality management is achieved through:

- a) Implementation of management systems in accordance with, but not limited to ISO 9001, ISO 14001, and ISO 45001/OHSA 18001 requirements;
- b) fulfilling performance and compliance obligations/legal and other requirements to which Eskom subscribes and sets to meet the intent of this policy;
- c) taking overall responsibility and accountability for the prevention of work-related injury and ill health, as well as the provision of safe and healthier workplaces and activities;
- d) addressing the needs and expectations of Eskom's workers, customers, interested parties, and stakeholders;
- e) setting safety, health, environment and quality objectives to achieve intended outcomes and measuring performance against these to ensure continual improvement;
- f) applying risk-based assessment methodologies (that is, conducting hazard identification and risk assessment, fitness for duty assessments, emergency preparedness responses, response to emerging outbreaks, pandemic or epidemic disasters, and medical surveillance) for the opportunity for improvement within the SHEQ management systems;
- g) conducting safety, health, environment and quality training and creating employee awareness;
- h) engaging interested parties and stakeholders by promoting open communication and engagement that is safety, health, environment and quality purpose-driven;
- i) ensuring that processes are in place and measured for Eskom's contractors to meet Eskom's safety, health, environment and quality requirements;
- j) ensuring that adequate resources are available for safety, health, environment and quality management;
- k) supporting the establishment and functioning of environment, quality, health and safety committees;
- l) proactively managing Eskom's environmental footprint, minimizing pollution and environmental degradation, pursuing a low-carbon future, and prioritizing energy, water efficiency, and conservation within and outside Eskom including transitioning to a cleaner energy mix;
- m) engaging, directing, and supporting persons to contribute to the effective management of SHEQ requirements;
- n) ensuring the sustainable use of resources and exploring new opportunities for climate change mitigation and adaptation, and protection of biodiversity, ecosystems, and the prevention of pollution and degradation;
- o) ensuring continual improvement in SHEQ systems to enhance Eskom's business performance; and
- p) consultation and participation of workers and worker representatives on OH&S management systems.

Policy principles or rules

Eskom's principles and rules that underpin the way it approaches safety, health, environment and quality are as follows:

- a) Poor quality performance and occupational health, safety and environmental incidents are preventable.
- b) SHEQ performance is achieved through a Zero Harm culture. Zero Harm is the prevention of harm to people and the environment brought about through visible and felt leadership, including the implementation of effective controls and practices.
- c) Management is accountable for setting a safety, health, environment and quality policy, and every employee is expected to ensure implementation and compliance within the scope of their duties.
- d) Conducting business with respect and care for people, the environment and assets.
- e) Eskom strives to ensure that Zero Harm befalls its employees, contractors, the public, and the environment:
 - Zero fatalities
 - Zero injuries, ill health
 - Zero environmental incidents
 - Zero tolerance
 - Zero defects
- f) Eskom's Life-Saving Rules support the intent of the policy and apply to all employees, contractors, and visitors:
 - Open, isolate, test, earth, bond, and/or insulate before touch
 - Hook up at heights
 - Buckle up
 - Be sober
 - Permit to work
- g) No operating condition, or urgency of service, justifies exposing anyone to risks arising out of Eskom's business, causing an incident with health, safety, environmental and quality consequences.
- h) Governance, decision-making processes, and plans are based on intended outcomes with regard to safety, health, environment and quality and criteria in line with Eskom values and promote efficiency.

André de Ruyter

GROUP CHIEF EXECUTIVE

Issued by Risk & Sustainability Division October 2020 SHEQ Policy Poster Rev 6 (Review Date October 2025)

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

48. Annexure C: Acknowledgement Form for Eskom OHS Rules & Other Legislative Requirements:

1. It is the duty of the DS&I Contractor and all contractors to ensure that they are familiar with the relevant OHS legislations required in accordance with the scope of the project.

The DS&I Contractor shall compile an OHS legal register listing all applicable statutory requirements (local by-laws, provincial, national and/or international) based on the scope of work that they are contracted for. The register shall be updated at intervals defined by the DS&I Contractor.

Please note that there will be Eskom Site Specific requirements that will be made available to the DS&I Contractor for consideration due to the fact that this scope of work will be conducted on an existing Eskom site.

I, the undersigned, hereby confirm that I, on behalf of
(Name of DS&I Contractor Company) will comply with the relevant applicable legislation, specifications and standards in accordance with the scope of the project and fully understand the consequences of non-compliance.

Signed at on Day of 20.....

Name of Authorised person (CEO/Director/ Managing Director)

Signature

Date

Witness 1

Witness 2

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.

49. Annexure D: Emergency Services contact details around Vereeniging:

Emergency Services	Contact number.	Distance from Site	Comments
Police Viljoensdrift	016 974 6261 (Free State)		
Vereeniging Mediclinic	016 440 5000		
Fire Brigade	016 430 1816		
Traffic department	016 450 3347		
SAPS Toll Free	10111		
Department Of Labour	016 430 0000		
Ambulance Toll Free	10177		
ER 24	084124		

CONTROLLED DISCLOSURE

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Limited, Reg No 2002/015527/06.