

 <b>Eskom</b>	<b>Template</b>	<b>Project Engineering</b>
--	-----------------	----------------------------

Title: <b>TECHNICAL EVALUATION CRITERIA FOR CABLING REQUIREMENTS FOR MERCURY 3RD400/132KV TRANSFORMER – MERCURY SS</b>	Template Identifier:	<b>240-180000669</b>
	Unique Identifier:	<b>Mer23P13</b>
	Area of Applicability:	<b>Engineering</b>
	Documentation Type:	<b>Template</b>
	Revision:	<b>1</b>
	Total Pages:	<b>27</b>
	Disclosure Classification:	<b>Controlled Disclosure</b>

**Compiled by**



**Christinah Mohloki**

**Chief Project Engineer:  
Planning & Project Support**

**Functional Responsibility**



**Vanessa Naidu**

**Middle Manager: Planning  
& Project Support**

**Authorized by**



**Judith Malinga**

**Senior Manager: PTM&C  
Engineering**

Date: 18 April 2024

Date: 18/04/2024

Date: 19/04/2024

<b>Content</b>	<b>Page</b>
1. Introduction .....	4
2. Supporting clause .....	4
2.1 Scope .....	4
2.2 Normative/informative references .....	4
2.3 Definitions .....	5
2.4 Abbreviations .....	5
2.5 Roles and responsibilities .....	5
2.6 Process for monitoring .....	5
2.7 Related/supporting documents .....	5
3. Technical Tender Evaluation Procedure .....	5
4. Stage 1: Evaluation of Technical Qualitative Requirements for the supply of cables .....	6
4.1 Stage 1 Subcategory 1: Cabling supplied as per cable block diagrams .....	7
4.2 Stage 1 Subcategory 2: Cable Types .....	8
5. Stage 2: Evaluation of Technical Qualitative Requirements for Cable Installation, Termination and other cable associated activities .....	11
6. Stage 3: Deemed Offer Risk(s) .....	12
7. Authorization .....	13
8. Revision History .....	13
9. Acknowledgements .....	13
Annexure A: A&B Technical Schedule .....	14
Annexure B: Schedule for cable types .....	16
Annexure C: Cabling - Relevant Experience and capability .....	19
Annexure D: Cabling- Qualifications and Experience of Key personnel .....	20
Annexure E: Procedure for Cable Installation .....	21
Annexure F: Procedure for Cable Termination .....	22
Annexure G: Procedure for Loading and unloading cable drums .....	23
Annexure H: Procedure for cable handling and storing .....	24
Annexure I: Cabling - Tools and Equipment .....	25
Annexure J: Procedure for removing old cables .....	26
Annexure K: Deviation Schedule .....	27
<b>Tables</b>	
Table 1: Scoring of Items in Technical Schedules A&B .....	7
Table 2: Technical Qualitative Requirements for the supply of cables Evaluation .....	7
Table 3: List of cables and approved suppliers .....	8
Table 4: List of fibre cables and approved suppliers .....	9
Table 5: Scoring of Items for the cable schedule .....	9
Table 6: Technical Qualitative requirement for the cable types schedule .....	10
Table 7: Scoring Allocation for Cabling .....	11

---

Table 8: Technical Qualitative Scoring for Cable Installation, Termination and other cable activities .....	12
Table 9: Deemed Offer Risk(s) Evaluation .....	13

18/04/2024

## 1. Introduction

This document provides an overview of Eskom's technical evaluation strategy and criteria to be used when evaluating the tender submissions for:

- a. Supply, delivery, installation and termination of cabling as detailed in 240-170001091 High Level Scope of Work – PTM&C Equipment for Mercury Substation Supporting clause.
- b.

### 1.1 Scope

This document contains the technical evaluation strategy and criteria relating to,

- a. Supply, delivery, installation and termination of cabling as detailed in 240-170001091 High Level Scope of Work – PTM&C Equipment for Mercury Substation

and details specific tender returnable required to facilitate this evaluation.

#### 1.1.1 Purpose

The purpose of this document is to define the technical evaluation strategy and criteria and detail specific tender returnable required to facilitate this evaluation.

#### 1.1.2 Applicability

This document shall apply to Eskom Transmission Division.

## 1.2 Normative/informative references

Parties using this document shall apply:

### 1.2.1 Normative

Note: Certain documents listed below may state applicability to Eskom Distribution, however those documents are also applicable to Eskom Transmission.

- [1] 240-170001091 High Level Scope of Work – PTM&C Equipment for Mercury Substation.
- [2] SANS-10198: The Selection, Handling and Installation of Power Cables not exceeding 33kV
- [3] 240-56063805 – LV Power and Control Cables with Rated Voltage Standard 600/1000 V
- [4] 240-56030637– General Information and Requirements for Low Voltage Cable System Standard
- [5] 240-64636794 – Standard for wiring and Cable Marking in Substations
- [6] 240-46425213 – Cable Testing Control plant
- [7] 240-168928041 – Secondary Cable Removal Strategy in Western Grid
- [8] 240-72274830 - Multimode Fibre Optic Duct Cable Specification
- [9] NRS 088-1, Duct and direct-buried underground fibre-optic cable – Part 1: Product specification ( **note: Eskom requirement unarmoured**)
- [10] 240- 64813646: Data Cable Required for X.21 Interfaces.

## 1.3 Definitions

### 1.3.1 General

Definition	Description
<b>Double Busbar</b>	A substation layout consisting of the conventional double busbar configuration with bus section, bus couplers etc. A set of isolator links per busbar are used to connect the transformer bay to either busbar. In double bus bar system two identical bus bars are used in such a way that any outgoing or incoming feeder can be taken from any of the bus.
<b>Extra High Voltage</b>	Nominal AC voltages above 220kV up to and including 765kV.

### 1.3.2 Disclosure classification

**Controlled disclosure:** controlled disclosure to external parties (either enforced by law, or discretionary).

## 1.4 Abbreviations

Abbreviation	Description
<b>kV</b>	Kilovolt
<b>PTM&amp;C</b>	Protection Telecommunications Measurements & Control

## 1.5 Roles and responsibilities

It is proposed that:

- Eskom shall utilise this document as the basis for the technical evaluation process.
- Tenderers shall note the evaluation criteria and required tender returnables as laid out in this document and submit tenders in compliance to the stipulated requirements.

## 1.6 Process for monitoring

Not applicable.

## 1.7 Related/supporting documents

Not applicable.

## 2. Technical Tender Evaluation Procedure

The evaluation process has three stages, with a corresponding minimum score (threshold) required for a bid to be deemed compliant are:

a. **Stage 1:** Stage 1 has two subcategories:

1. Technical Qualitative Requirements for the supply of cables as cable block diagrams included in the scope which require a minimum of 80% compliance threshold. Only submissions that pass the scoring threshold of a minimum of 80% will proceed to the next subcategory.
2. Technical Qualitative Requirements for the type of cable supplied which require a minimum of 80% compliance threshold. Only submissions that pass the scoring threshold of a minimum of 80% will proceed to the next stage.

- b. **Stage 2:** Technical Qualitative Requirements for Cable Installation, Termination and other cable associated activities which require a minimum of 80% compliance threshold. Only submissions that pass the scoring threshold of a minimum of 80% will proceed to the next stage.
- c. **Stage 3:** Deemed offer Risks which should at least be acceptable.

The technical evaluation process will follow a chronological order:

- 1) Stage 1 evaluates the technical criteria for the supply of cables and will be scored against the thresholds defined. If the Stage 1 threshold is met, then the qualifying bid will proceed to Stage 2. If the bidder fails to achieve the defined threshold, then the submission is deemed to be non-compliant and will not be considered for further evaluation. Based on the evaluation, qualifying offers with any non-compliances which Eskom deems necessary, may be recommended for negotiation as compulsory prior to contract award.
- 2) Stage 2 evaluates the technical criteria for Cable Installation, Termination and other cable associated activities will be scored against the thresholds defined. If the Stage 2 thresholds are met, then the qualifying bids will proceed to Stage 3. If the bidder fails to achieve the defined threshold, then the submission is deemed to be non-compliant and will be removed from further evaluation. Based on the evaluation, qualifying offers with any non-compliances which Eskom deems necessary, may be recommended for negotiation as compulsory prior to contract award.
- 3) Stage 3 is a report written by the evaluation team to determine and motivate whether any risks found throughout the evaluation are deemed low / acceptable / high and will serve as input to the recommendation as to whether the offer should be accepted.

The detailed methodologies for scoring in each stage are provided in Sections 4 to 6.

### 3. Stage 1: Evaluation of Technical Qualitative Requirements for the supply of cables

Stage 1 has two subcategories which will be evaluated.

The following returnables must be completed, signed, and submitted:

1. Annexure A: A&B Technical Schedule
2. Annexure B: Schedule for Cable types
3. Annexure K: Deviation Schedule

**3.1 Stage 1 Subcategory 1: Cabling supplied as per cable block diagrams**

The required cable blocks are in the scheme package drawings provided with 240-170001091 High Level Scope of Work – PTM&C Equipment for Mercury Substation.

The following criteria will be used to assess the tenderer's technical capability to enter a contract with Eskom with respect to the supply of specific products to meet Eskom's requirements.

Each item will be assigned a score by the Eskom evaluation team, based upon the tendered response, using Table 1.

Tender responses claiming compliance to an item (e.g., 'Comply') but which are found to be non-compliant during verification will be assigned the corresponding score by the Eskom evaluation team. Items for which compliance is not claimed (e.g., 'Do Not Comply'), but which are found to be compliant during verification will be scored as 'non-compliant' based on the original response.

All scores for Annexure A: A&B Technical Schedule, will be tallied and shall be calculated based on the maximum possible score as indicated in Table 2. There is a minimum score threshold of 80% to pass this subcategory and proceed to the next subcategory.

**Table 1: Scoring of Items in Technical Schedules A&B**

Criteria	Score
Fully compliant	1
Non-compliant (major deviation)	0

**Table 2: Technical Qualitative Requirements for the supply of cables Evaluation**

No.	Item	Score (1/0)	Comments
1.	Full compliance to 0.52/30434 and 0.52/30459, in respect of equipment supplied and wiring.		
2.	Full compliance to Drawing No: 0.52/30564 and 0.52/30565, in respect of equipment supplied and wiring.		
3.	Full compliance to Drawing No: 0.52/30566 and 0.52/30567, in respect of equipment supplied and wiring.		
4.	Full compliance to Drawing No: 0.52/30570, in respect of equipment supplied and wiring.		
5.	Full compliance to Drawing No: 0.52/30448, in respect of equipment supplied and wiring.		
6.	Full compliance to Drawing No: 0.52/30795, in respect of equipment supplied and wiring.		
7.	Full compliance to Drawing No: 0. 0.52/30794, in respect of equipment supplied and wiring.		
8.	Full compliance to Drawing No: 0.52/30793, in respect of equipment supplied and wiring.		
9.	Full compliance to Drawing No: 0.52/30578 & 0.52/30579, in respect of equipment supplied and wiring.		

**ESKOM COPYRIGHT PROTECTED**

**TECHNICAL EVALUATION CRITERIA FOR CABLING  
REQUIREMENTS FOR MERCURY 3RD400/132KV  
TRANSFORMER – MERCURY SS**
Unique Identifier: **Mer23P13**Revision: **1**Page: **8 of 27**

No.	Item	Score (1/0)	Comments
10.	Full compliance to Drawing No: 0.52/30580 & 0.52/30581, in respect of equipment supplied and wiring.		
11.	Full compliance to Drawing No: 0.52/30513 & 0.52/30514, in respect of equipment supplied, wiring and frequency.		
Total Score %			<b>Threshold = 80%</b>

### 3.2 Stage 1 Subcategory 2: Cable Types

The cables supplied must conform to *240-56063805 LV Power and control cable with rated voltage standard*. Table 3 details the cables which have been accepted for use in Transmission substations. Eskom contracted suppliers are included for reference in Table 3.

**Table 3: List of cables and approved suppliers**

Cable Code	Cable Description	Eskom Supplier
BVX12DCV	CABLE ELECT:1 KV;12C;CU;2.5 MM2;STL WIRE	CBI
BVX12ECV	CABLE ELECT:1 KV;12C;CU;4 MM2;STL WIRE	CBI, M-TEC
BVX19DCV	CABLE ELECT:1 KV;19C;CU;2.5 MM2;STL WIRE	CBI, M-TEC
BVX19ECV	CABLE ELECT:1 KV;19C;CU;4 MM2;STL WIRE	CBI, M-TEC
BVX2HCV	CABLE ELECT:1 KV;2C;CU;16 MM2;STL WIRE	CBI
BVX4GCV	CABLE ELECT:1 KV;4C;CU;10 MM2;STL WIRE	CBI
BVX2ECV	CABLE ELECT:1 KV;2C;CU;4 MM2;STL WIRE	CBI
BVX37DCV	CABLE ELECT:1 KV;37C;CU;2.5 MM2;STL WIRE	CBI
BVX4NCV	CABLE ELECT:1 KV;4C;CU;4 MM2;STL WIRE	CBI
BVX4HCV	CABLE ELECT:1 KV;4C;CU;16 MM2;STL WIRE	CBI
BVX4DCV	CABLE ELECT:1 KV;4C;CU;2.5 MM2;STL WIRE	CBI
BVX4KCV	CABLE ELECT:1 KV;4C;CU;25 MM2;STL WIRE	CBI
BVX4ECV	CABLE ELECT:1 KV;4C;CU;4 MM2;STL WIRE	CBI
BVX7DCV	CABLE ELECT:1 KV;7C;CU;2.5 MM2;STL WIRE	CBI, Aberedare
BVX4QCV	CABLE ELECT:1 KV;4C;CU;120 MM2;STL WIRE	CBI
BVX7ECV	CABLE ELECT:1 KV;7C;CU;4 MM2;STL WIRE	CBI, MTEC

**ESKOM COPYRIGHT PROTECTED**



**TECHNICAL EVALUATION CRITERIA FOR CABLING  
REQUIREMENTS FOR MERCURY 3RD400/132KV  
TRANSFORMER – MERCURY SS**
Unique Identifier: **Mer23P13**Revision: **1**Page: **9 of 27**

Cable Code	Cable Description	Eskom Supplier
BVX4LCV	CABLE ELECT:1 KV;4C;CU;35 MM2;STL WIRE	CBI
BVX37ECV	CABLE ELECT:1 KV;37C;CU;4 MM2;STL WIRE	CBI, Aberedare

Eskom utilises 2 types of Duct Fibre Optic cables, which are multimode and single mode. The multimode cable is rodent resistance and shall conform to Eskom specification 240-72274830 Multimode Fibre Optic Duct Cable Specification. The single mode cable may be rodent resistant or not as per application, but it may not have any shielding/armouring. This single mode cable shall conform to NRS 088-1 (2019) Duct and Direct Buried Underground Fibre Optic Specification. The types of fibre cables are listed in Table 4 with the Eskom approved suppliers.

**Table 4: List of fibre cables and approved suppliers**

Cable Code	Cable Description	Eskom approved suppliers
8 core Single mode double sheath	Cable fibre OPTC:HDD; 8; DOUBLE; 9/125	CBI, AMHT, DartCom, WTD
12 core Single mode double sheath	Cable fibre OPTC:HDD; 12; DOUBLE; 9/125	CBI, AMHT, DartCom, WTD
48 core Single mode double sheath	Cable fibre OPTC:HDD; 48; DOUBLE; 9/125	CBI, AMHT, DartCom, WTD
8 core Single mode HDD	Cable fibre OPTC:HDD; 8; HDD; 9/125	CBI, AMHT, DartCom, MTEC
24 core Single mode HDD	Cable fibre OPTC:HDD; 24; HDD; 9/125	CBI, AMHT, DartCom, MTEC
48 core Single mode HDD	Cable fibre OPTC:HDD; 48; HDD; 9/125	CBI, AMHT, DartCom, MTEC
12 core multimode double sheath	Cable fibre OPTC:HDD; 12; DOUBLE; 50/125	CBI, AMHT, DartCom, WTD

The following criteria will be used to assess the tenderer's technical capability to enter a contract with Eskom with respect to the supply of specific products to meet Eskom's requirements.

Each item will be assigned a score by the Eskom evaluation team, based upon the tendered response, using Table 5.

**Table 5: Scoring of Items for the cable schedule**

Criteria	Score
Fully compliant	1
Non-compliant (major deviation)	0

Tender responses claiming compliance to an item (e.g., 'Comply') but which are found to be non-compliant during verification will be assigned the corresponding score by the Eskom evaluation team. Items for which compliance is not claimed (e.g., 'Do Not Comply'), but which are found to be compliant during verification will be scored as 'non-compliant' based on the original response.

**ESKOM COPYRIGHT PROTECTED**

All scores for Annexure B: Schedule for cable types will be tallied and shall be calculated based on the maximum possible using Table 6. There is a minimum score threshold of 80% to pass this subcategory and proceed to the next stage.

**Table 6: Technical Qualitative requirement for the cable types schedule**

No.	Item	Score (1/0)	Comments
1.	Full compliance to BVX12DCV, in respect of cable procured		
2.	Full compliance to BVX12ECV, in respect of cable procured		
3.	Full compliance to BVX19DCV in respect of cable procured		
4.	Full compliance to BVX19ECV in respect of cable procured		
5.	Full compliance to BVX2HCV, in respect of cable procured		
6.	Full compliance to BVX4GCV, in respect of cable procured		
7.	Full compliance to BVX2ECV, in respect of cable procured		
8.	Full compliance to BVX37DCV, in respect of cable procured		
9.	Full compliance to BVX4NCV, in respect of cable procured		
10.	Full compliance to BVX4HCV, in respect of cable procured		
11.	Full compliance to BVX4DCV, in respect of cable procured		
12.	Full compliance to BVX4KCV, in respect of cable procured		
13.	Full compliance to BVX4ECV, in respect of cable procured		
14.	Full compliance to BVX7DCV, in respect of cable procured		
15.	Full compliance to BVX4QCV, in respect of cable procured		
16.	Full compliance to BVX7ECV, in respect of cable procured		
17.	Full compliance to BVX4LCV, in respect of cable procured		
18.	Full compliance to BVX37ECV, in respect of cable procured		
19.	Full compliance to 8 core Single mode double sheath in respect of cable procured		
20.	Full compliance to 12 core Single mode double sheath, in respect of cable procured		
21.	Full compliance to 48 core Single mode double sheath, in respect of cable procured		
22.	Full compliance to 8 core Single mode HDD, in respect of cable procured		

No.	Item	Score (1/0)	Comments
23.	Full compliance to 24 core Single mode HDD in respect of cable procured		
24.	Full compliance to 48 core Single mode HDD, in respect of cable procured		
25.	Full compliance to 12 core multimode double sheath, in respect of cable procured		
Total Score %			<b>Threshold = 80%</b>

#### 4. Stage 2: Evaluation of Technical Qualitative Requirements for Cable Installation, Termination and other cable associated activities

This section contains the technical evaluation strategy and criteria for evaluating submissions to perform installation, termination and other associated activities of the equipment listed in detailed in 240-170001091 High Level Scope of Work – PTM&C Equipment for Mercury Substation at Eskom substations.

The following criteria will be used to assess the tenderer's technical capability to enter a contract with Eskom with respect to cable installation, termination and other cable related activities. The assessment is based on the returnables requested in:

1. Annexure C: Cabling - Relevant Experience and capability
2. Annexure D: Cabling- Qualifications and Experience of Key personnel
3. Annexure E: Procedure for Cable Installation
4. Annexure F: Procedure for Cable Termination
5. Annexure G: Procedure for Loading and unloading cable drums
6. Annexure H: Procedure for cable handling and storing
7. Annexure I: Cabling - Tools and Equipment
8. Annexure J: Procedure for removing old cables
9. Annexure K: Deviation Schedule

Each Annexure will be assigned a score by the Eskom evaluation team using Table 7. The score for each item will be multiplied by its weight to obtain the total score per item.

**Table 7: Scoring Allocation for Cabling**

Score	Description
10	Deemed to fully meet requirements
7	Deemed to mostly meet requirements
2	Deemed as substantially not meeting requirements
0	Nonresponsive
Note: Scores will be allocated in the range 0 - 10 with the above as a guideline	

The cabling criteria will be adjudicated as a weighted score out of 100% and will comprise of scoring in the categories as defined in Table 8. Each category has a minimum threshold score of 80%.

**Table 8: Technical Qualitative Scoring for Cable Installation, Termination and other cable activities**

Qualitative Technical Criteria Description		Minimum Threshold Score	Score	Criteria Sub Weighting (%)	Criteria Weighting (%)
<b>Relevant company experience (Projects completed in past 10 years)</b>		<b>80%</b>		-	<b>20</b>
1.1	Number of projects			10	
1.2	Project scope			10	
<b>Qualifications and experience of key personnel</b>		<b>80%</b>			<b>20</b>
2.1	Academic qualifications			5	
2.2	Project-specific work experience			15	
<b>Procedure for Cable Installation</b>		<b>80%</b>			<b>15</b>
3.1	Yard stone handling			5	
3.2	Trench cover handling			5	
3.3	Cable glanding & numbering			5	
<b>Procedure for Cable Termination</b>		<b>80%</b>			<b>10</b>
4.1	Handling of spare cores			5	
4.2	Ferrule numbering			5	
<b>Procedure for loading and unloading of cable drums</b>		<b>80%</b>			<b>5</b>
5.1	Adequacy of procedure			5	
<b>Procedure for cable handling and storing</b>		<b>80%</b>			<b>5</b>
6.1	Adequacy of procedure			5	
<b>Tools and equipment</b>		<b>80%</b>			<b>10</b>
7.1	Adequacy of tools and equipment and test certificate of crimping tools			10	
<b>Procedure for removing of old cables</b>		<b>80%</b>			<b>15</b>
8.1	Adequacy of procedure			15	
Total Score %					100%

## 5. Stage 3: Deemed Offer Risk(s)

Eskom's evaluation team shall compile a report summarising risks associated with any aspect of the offer:

- noted during the Technical Qualitative Requirements for the supply of cables,
- noted during the Technical Qualitative Requirements for Cable Installation, Termination and other cable associated activities

**ESKOM COPYRIGHT PROTECTED**

- c) based on any pricing anomalies, noted during the subsequent financial evaluation that cannot be acceptably clarified.
- d) Noted on the deviation schedule as in Annexure K: Deviation Schedule

This narrative shall be used to determine and motivate whether the risk is deemed high / acceptable / low and will serve as input to the recommendation as to whether the offer should be accepted as shown in Table 9 below. Note, the TET shall only have access to financial information post completion of the technical evaluation report. Any changes as a result of c) above will be included in an update to the initial report.

**Table 9: Deemed Offer Risk(s) Evaluation**

Criteria	Score	Comments
Deemed Offer Risk(s)		
Threshold	Acceptable	

## 6. Authorization

This document has been seen and accepted by:

Name and surname	Designation
Mario Petersen	Planning and Project Support Manager (Acting)
Quinton Labuschagne	Substation Automation Integration Manager

## 7. Revision History

Date	Rev	Compiler	Remarks
January	2023	K Jagdaw	Developed the template

## 8. Acknowledgements

Clive Watson

Mario Petersen

**Annexure A: A&B Technical Schedule**

This Annexure must be completed, signed and submitted.

Schedule A: Purchasers specific requirements. Each of these requirements are equally weighted.

Schedule B: Tenders to stipulate “**Comply**” or “**Do not Comply**”. All equipment supplied must be identical to the master drawings and wired identically in order to respond “**Comply**”.

No.	Requirements	Description	Schedule A	Schedule B	Comments
1.	Full compliance to Drawing No 0.12/08292, in respect of cable block diagrams and cable supplied.	Master Drawings for cable block diagrams and cables supplied	Comply		
2.	Full compliance to Drawing No 0.12/08293, in respect of cable block diagrams and cable supplied.	Master Drawings for cable block diagrams and cables supplied	Comply		
3.	Full compliance to Drawing No 0.12/08294, in respect of cable block diagrams and cable supplied.	Master Drawings for cable block diagrams and cables supplied	Comply		
4.	Full compliance to Drawing No 0.12/08295, in respect of cable block diagrams and cable supplied.	Master Drawings for cable block diagrams and cables supplied	Comply		
5.	Full compliance to Drawing No 0.12/08302, in respect of cable block diagrams and cable supplied.	Master Drawings for cable block diagrams and cables supplied	Comply		
6.	Full compliance to Drawing No: 0.12/08296, in respect of cable block diagrams and cable supplied.	Master Drawings for cable block diagrams and cables supplied	Comply		

**ESKOM COPYRIGHT PROTECTED**

**TECHNICAL EVALUATION CRITERIA FOR CABLING REQUIREMENTS FOR MERCURY  
3RD400/132KV TRANSFORMER – MERCURY SS**

Unique Identifier: **Mer23P13**

Revision: **1**

Page: **15 of 27**

No.	Requirements	Description	Schedule A	Schedule B	Comments
7.	Full compliance to Drawing No 0.12/7460, in respect of cable block diagrams and cable supplied.	Master Drawings for cable block diagrams and cables supplied	Comply		
8.	Full compliance to Drawing No 0.12/7228, in respect of cable block diagrams and cable supplied.	Master Drawings for cable block diagrams and cables supplied	Comply		
9.	Full compliance to Drawing No 0.12/7588, in respect of cable block diagrams and cable supplied.	Master Drawings for cable block diagrams and cables supplied	Comply		

Signed by: \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

**ESKOM COPYRIGHT PROTECTED**

**Annexure B: Schedule for cable types**

This Annexure must be completed, signed and submitted.

Schedule A: Purchasers specific requirements. Each of these requirements are equally weighted.

Schedule B: Tenders to stipulate “**Comply**” or “**Do not Comply**”. All cables supplied must be identical to the master drawings and procured from the Eskom approved suppliers order to respond “**Comply**”.

No.	Requirements	Description	Schedule A	Schedule B	Comments
1.	Full compliance to BVX12DCV, in respect of cable procured	CABLE ELECT:1 KV;12C;CU;2.5 MM2;STL WIRE	Comply		
2.	Full compliance to BVX12ECV, in respect of cable procured	CABLE ELECT:1 KV;12C;CU;4 MM2;STL WIRE	Comply		
3.	Full compliance to BVX19DCV in respect of cable procured	CABLE ELECT:1 KV;19C;CU;2.5 MM2;STL WIRE	Comply		
4.	Full compliance to BVX19ECV in respect of cable procured	CABLE ELECT:1 KV;19C;CU;4 MM2;STL WIRE	Comply		
5.	Full compliance to BVX2HCV, in respect of cable procured	CABLE ELECT:1 KV;2C;CU;16 MM2;STL WIRE	Comply		
6.	Full compliance to BVX4GCV, in respect of cable procured	CABLE ELECT:1 KV;4C;CU;10 MM2;STL WIRE	Comply		
7.	Full compliance to BVX2ECV, in respect of cable procured	CABLE ELECT:1 KV;2C;CU;4 MM2;STL WIRE	Comply		
8.	Full compliance to BVX37DCV, in respect of cable procured	CABLE ELECT:1 KV;37C;CU;2.5 MM2;STL WIRE	Comply		
9.	Full compliance to BVX4NCV, in respect of cable procured	CABLE ELECT:1 KV;4C;CU;4 MM2;STL WIRE	Comply		

**ESKOM COPYRIGHT PROTECTED**



**TECHNICAL EVALUATION CRITERIA FOR CABLING REQUIREMENTS FOR MERCURY  
3RD400/132KV TRANSFORMER – MERCURY SS**

Unique Identifier: **Mer23P13**

Revision: **1**

Page: **17 of 27**

No.	Requirements	Description	Schedule A	Schedule B	Comments
10.	Full compliance to BVX4HCV, in respect of cable procured	CABLE ELECT:1 KV;4C;CU;16 MM2;STL WIRE	Comply		
11.	Full compliance to BVX4DCV, in respect of cable procured	CABLE ELECT:1 KV;4C;CU;2.5 MM2;STL WIRE	Comply		
12.	Full compliance to BVX4KCV, in respect of cable procured	CABLE ELECT:1 KV;4C;CU;25 MM2;STL WIRE	Comply		
13.	Full compliance to BVX4ECV, in respect of cable procured	CABLE ELECT:1 KV;4C;CU;4 MM2;STL WIRE	Comply		
14.	Full compliance to BVX7DCV, in respect of cable procured	CABLE ELECT:1 KV;7C;CU;2.5 MM2;STL WIRE	Comply		
15.	Full compliance to BVX4QCV, in respect of cable procured	CABLE ELECT:1 KV;4C;CU;120 MM2;STL WIRE	Comply		
16.	Full compliance to BVX7ECV, in respect of cable procured	CABLE ELECT:1 KV;7C;CU;4 MM2;STL WIRE	Comply		
17.	Full compliance to BVX4LCV, in respect of cable procured	CABLE ELECT:1 KV;4C;CU;35 MM2;STL WIRE	Comply		
18.	Full compliance to BVX37ECV, in respect of cable procured	CABLE ELECT:1 KV;37C;CU;4 MM2;STL WIRE	Comply		
19.	Full compliance to 8 core Single mode double sheath in respect of cable procured	Cable fibre OPTC:HDD; 8; DOUBLE; 9/125	Comply		
20.	Full compliance to 12 core Single mode double sheath, in respect of cable procured	Cable fibre OPTC:HDD; 12; DOUBLE; 9/125	Comply		
21.	Full compliance to 48 core Single mode double sheath, in respect of cable procured	Cable fibre OPTC:HDD; 48; DOUBLE; 9/125	Comply		
22.	Full compliance to 8 core Single mode HDD, in respect of cable procured	Cable fibre OPTC:HDD; 8; HDD; 9/125	Comply		

**ESKOM COPYRIGHT PROTECTED**

**TECHNICAL EVALUATION CRITERIA FOR CABLING REQUIREMENTS FOR MERCURY  
3RD400/132KV TRANSFORMER – MERCURY SS**

Unique Identifier: **Mer23P13**

Revision: **1**

Page: **18 of 27**

No.	Requirements	Description	Schedule A	Schedule B	Comments
23.	Full compliance to 24 core Single mode HDD in respect of cable procured	Cable fibre OPTC:HDD; 24; HDD; 9/125	Comply		
24.	Full compliance to 48 core Single mode HDD, in respect of cable procured	Cable fibre OPTC:HDD; 48; HDD; 9/125	Comply		
25.	Full compliance to 12 core multimode double sheath, in respect of cable procured	Cable fibre OPTC:HDD; 12; DOUBLE; 50/125	Comply		

Signed by: \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

**ESKOM COPYRIGHT PROTECTED**

When downloaded from the WEB, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the WEB.

### Annexure C: Cabling - Relevant Experience and capability

Submit three (not more) different sets of the below sheets for recent (within the last 3 years) **cabling** projects you have conducted (e.g. three different Transmission Projects). The projects must be from different substations. Submissions with less than three sets of the below sheets would incur a penalty.

Tenderer Company Name		
What was the name of your business or company then?		
How many cabling Projects have you completed for Eskom?		
What was the name of the project?		
What was the substation name?		
What was the completion date?		
What was the Project Value?		
What were project scope of the site where you did the work (You may include GPS coordinates)?		
What are the contact details of the client that you did work for?	Name	
	Contact Person	
	Office and Cellphone numbers	
	Email address	
	Physical address	
Did you complete the work you did?		
Did you receive any non-conformances against you for the work you performed?		
<b>Signed:</b> _____ (Company Rep) <b>Date:</b> _____		
<b>Rep Name:</b> _____ <b>Tendering Company:</b> _____		

**ESKOM COPYRIGHT PROTECTED**

## Annexure D: Cabling- Qualifications and Experience of Key personnel

Please, complete this annexure indicating the training and courses related to this tendered project that each employee (to be involved with this tendered project) has undergone. Also provide a summary work experience specific to this project for each resource. Submit copies of the training certificates and these copies must be certified by the Commissioner of Oaths, with a signature and date not older than three months from the tender closing date. Training certificates need to be still valid on the date of tender close. Certificates that have expired prior to this date would not be accepted as valid evidence.

Name and surname of the resource.				
Position held				
Academic qualification				
Will this resource be dedicated to the project?				
Total Number of resources dedicated to the project?				
Related training and courses completed by the resource.	Date obtained	Expiry date	<b>Max. Points</b>	<b>Obtained Points</b>
<b>Project Specific Work Experience for Resource</b>				
<b>Signed:</b> _____ (Company Rep) <b>Date:</b> _____				
<b>Rep Name:</b> _____ <b>Tendering Company:</b> _____				











**Annexure I: Cabling - Tools and Equipment**

Please, complete this annexure, and submit it with the tender document. Examples are provided below; however, this is not an exhaustive list. Ensure that you list all relevant tools and equipment required for the project.

Tools to be used for construction	Description	Requirement	Serial no.	Valid test / calibration certificate no.	Indicate if owned(O) or to be hired(H)**
Technicians Toolbox	Pliers, side cutters, insulated screw drivers, strippers, etc	Per Team			
Insulation Tester		Per Team			
JST Crimper >1mm ≤ 6mm		Per Team			
Hexagon Crimper ≥ 6mm					
Multimeter.		Per Team			
Splicing Machine		Per Team			
Optical Time Domain Reflector (OTDR)		Per Team			
Power Meter or Light Source					

**\*\*When tools would be hired, a hiring letter from the reputable hiring agency is required**

**DECLARATION:** I hereby confirm that the tools list above is a true reflection of the tools owned or hired by my Company.

I will also ensure that all tools will be enough to cater for multiple full teams and tools that require calibration will have valid calibration certificates before the execution of work.

**Signed:** \_\_\_\_\_ (Company Rep)

**Rep Name:** \_\_\_\_\_

**Date:** \_\_\_\_\_



